

2005 4th QUARTER GROUNDWATER MONITORING REPORT

**FORMER ANGELES CHEMICAL COMPANY FACILITY
8915 SORENSEN AVENUE SANTA FE SPRINGS, CALIFORNIA**

Prepared and Submitted To:

**Department of Toxic Substances Control
1011 N. Grandview Avenue
Glendale, CA 91201**

On Behalf Of:

**Greve Financial Services
7101 Western Avenue
Buena Park, CA 90670**

Prepared By:

**The Leu Group
33725 Magellan Isle
Suite 100
Monarch Beach, CA 92629
(949) 248-5873**

MARCH 2006



**THE
LEU
GROUP**

Protecting Your
Quality of Life


2005 4TH QUARTER GROUNDWATER MONITORING REPORT

**Former Angeles Chemical Company Facility
8915 Sorensen Avenue, Santa Fe Springs, CA**

Prepared and Submitted to:
Department of Toxic Substances Control
1011 N. Grandview Avenue
Glendale, CA 91201

Prepared by:

David J. Leu, Ph.D.
Principal
The Leu Group



Mark Slatten, RG, CEG
Director of Field Operations
The Leu Group



The Leu Group
33725 Magellan Isle, Suite 100
Monarch Beach, CA 92629)

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	SITE DESCRIPTION	1
3.0	PREVIOUS SITE ASSESSMENT WORK	1
4.0	REGIONAL GEOLOGY/HYDROGEOLOGY	3
5.0	SITE GEOLOGY/HYDROGEOLOGY	4
6.0	GROUNDWATER MONITORING PROTOCOL	5
6.1	Well Purging and Measurement of Field Parameters	6
6.2	Well Sampling	7
6.3	Sample Handling	8
6.4	Waste Management	9
7.0	FREE PRODUCT	9
8.0	GROUNDWATER SAMPLE RESULTS	10
9.0	VOCS CAPTURED AND TREATED BY THE SVE SYSTEM	13
10.0	CONCLUSIONS	13
11.0	RECOMMENDATIONS	14

FIGURES

- Figure 1 Site Location Map
- Figure 2 Well Location Map
- Figure 3 First Water Potentiometric Gradient Map
- Figure 4 A1 Zone Potentiometric Gradient Map
- Figure 5 First Water Groundwater Elevations (Central & Northern Wells)
- Figure 6 First Water Groundwater Elevations (Southern Wells)
- Figure 7 Upper A1 Groundwater Elevations
- Figure 8 Lower A1 Groundwater Elevations
- Figure 9 TPH-g and BTEX Concentrations in First Water
- Figure 10 TPH-g and BTEX Concentrations in upper and Lower A1 Zones
- Figure 11 Chlorinated VOC's & 1,4 Dioxane Concentrations in First Water
- Figure 12 Chlorinated VOC's & 1,4 Dioxane Concentrations in a1 Zones
- Figure 13 Acetone, MEK and MIBK in First Water
- Figure 14 Acetone, MEK and MIBK in Upper and Lower A1 Zones

TABLE OF CONTENTS (cont.)

TABLES

- | | |
|---------|--|
| Table 1 | Well & Screen Elevations and Groundwater Depths and Elevations |
| Table 2 | TPH-gas and VOC's from Free Product |
| Table 3 | Conductivity, pH and TPH-gas Groundwater Results |
| Table 4 | Detected VOC's from Groundwater Results |
| Table 5 | Detected VOC's from Diffusion Bag Groundwater Samples |
| Table 6 | Biodegradation Indicator Results |
| Table 7 | Dissolved Metals |
| Table 8 | Free Product Removal Detail |

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 1**

1.0 INTRODUCTION

The Leu Group was contracted by Greve Financial Services (310) 753-5770 to perform quarterly groundwater monitoring at the former Angeles Chemical Company (ACC), Inc. facility located at 8915 Sorensen Avenue, Santa Fe Springs, California (See Figure 1, Site Location Map). The quarterly groundwater monitoring was requested by the Department of Toxics Substance Control (DTSC) correspondence dated September 18, 2001. This report presents the results of the 2005 4th quarter monitoring event performed on December 16, 2005.

Recently, Clean Soils, Inc., under contract to Greve Financial Services has started operating a 500 scfm soil vapor extraction (SVE) system at the ACC site. This report presents the amount of volatile organic compounds (VOCs) that have been extracted and treated by the SVE system during the 4th quarter, 2005.

2.0 SITE DESCRIPTION

The site is approximately 1.8 acres in size and completely fenced. The site is bound by Sorensen Avenue on the east, Air Liquide Corporation to the north and northwest, Plastall Metals Corporation to the north, and a Southern Pacific Railroad easement and McKesson Chemical Company to the south.

The ACC operated as a chemical repackaging facility from 1976 to 2000. A total of thirty-four (34) underground storage tanks (USTs) existed beneath the site. Two (2) USTs, one gasoline and one diesel, and sixteen (16) chemical USTs were excavated and removed under the oversight of the Santa Fe Springs Fire Department. All 16 remaining chemical USTs were decommissioned in place and slurry-filled.

3.0 PREVIOUS SITE ASSESSMENT WORK

In January 1990, SCS Engineers, Inc. (SCS) conducted a site investigation and drilled eight borings from 5 feet below grade surface (bgs) to 50 feet bgs. Soil samples collected and analyzed contained benzene, 1,1-Dichloroethane (1,1-DCA), 1,1-Dichloroethene (1,1-DCE), MEK, methyl isobutyl ketone (MIBK), toluene, 1,1,1-Trichloroethane (1,1,1-TCA), Tetrachloroethylene (PCE), and xylenes at detectable concentrations.

In June 1990, SCS conducted an additional site investigation at the site by advancing six additional borings drilled from 20.5 feet bgs to 60 feet bgs. A monitoring well (MW-1) was also installed. Soil sample analysis revealed detectable concentrations of the above mentioned VOCs in addition to acetone and methylene chloride. Dissolved

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 2**

benzene, 1,1-DCA, 1,1-DCE, PCE, Trichloroethylene (TCE), and trans-1,2-dichloroethene were detected in MW-1 above maximum contaminant levels.

Between 1993 and 1994, SCS conducted further testing at the site. Soil samples were collected from nine borings. Five borings were converted to groundwater monitoring wells MW-2, MW-3, MW-4, MW-6, and MW-7. The predominant compounds detected in soil and groundwater were acetone, MEK, MIBK, chlorinated VOCs, and BTEX.

In 1996 and 1999, SCS conducted separate soil vapor extraction (SVE) pilot tests using several treatment technologies on extraction well E-1 screened from 7 feet bgs and 22 feet bgs. Laboratory analysis identified maximum soil vapor gas concentrations as 1,1,1-TCA (30,300 ppmV) with detectable concentrations of 1,1-DCE, TCE, methylene chloride, toluene, PCE and xylenes. The radius of influence was measured between 35 and 80 feet.

In November 1997, SCS conducted a soil vapor survey (SVS) at the site. Soil vapor samples were collected at twenty-three locations at 5 feet bgs. In addition, soil vapor samples were collected at 15 feet bgs in five of the twelve sampling points. The SVS identified maximum VOC concentrations near the railroad tracks located on the northern portion of the site.

Blakely Environmental Investigations, Inc. (BEII) conducted an SVS at the site from November 27 to December 1, 2000. A total of 36 soil vapor sample points, labeled SV1 through SV36, were selected by BEII and approved by the DTSC for analysis. Two discrete soil vapor samples were collected from each soil vapor sample point, one at 8 feet bgs and one at 20 feet bgs. SV1 was an exception since the first soil vapor sample was collected at 10 feet bgs instead of 8 feet bgs. Based on the soil vapor sample results, BEII identified relatively low level concentrations of VOCs in the silty clay soils at 8 feet bgs. However, the concentrations of VOCs are significantly higher in the sandy soils at 20 feet bgs. Results were submitted to the DTSC by BEII in *Report of Findings*, dated January 10, 2001 with laboratory reports (BEII's *Report of Findings* dated January 10, 2001).

BEII conducted an additional SVS on the ACC site from January 14 to January 17, 2002. The purpose of the SVS was to determine the lateral extent of VOC soil vapors in the vadose zone along the eastern, northern, and southern property line of the site. In addition, BEII performed an SVS on June 13, 2002 on the Air Liquide property to determine the lateral extent of VOC soil vapors in the vadose zone north of the ACC facility. Based on the soil vapor survey results, BEII identified relatively low level concentrations of VOCs in the silty clay soils at 5-, 7-, 8-, 10-, and 12 feet bgs. However, the concentrations of VOCs are significantly higher in the sandy soils at 20 feet bgs, which are more permeable and conducive to soil vapor migration. Furthermore, VOC soil vapor concentrations were higher along the southern property line than along the east

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 3**

and north property line. Results were submitted by BEII to the DTSC in *Report of Findings*, dated October 15, 2002 with laboratory reports.

BEII drilled two soil borings (BSB-1 and BSB-2) and installed two groundwater monitoring wells (MW-8 and MW-9) on the ACC site from June 5 to June 7, 2002. The purpose of the drilling was to help define the lateral and vertical extent of impacted soil along the eastern ACC property line and to help determine the extent of impacted groundwater. Soil borings BSB-1 and BSB-2 were drilled to 50- and 30 feet bgs, respectively. Monitoring wells MW-8 and MW-9 were installed to 40.5- and 45.5 feet bgs, respectively. Soil sample results identified elevated VOC concentrations from monitoring well MW-8 at depth between 29- and 40 feet bgs. Results were submitted by BEII to the DTSC in a *Report of Findings* dated October 15, 2002 with laboratory reports.

BEII drilled eight soil borings (BSB-3 through BSB-10) and pushed eleven cone penetrometer test (CPT) locations (CPT-1 though CPT-11) in August 2002 to help determine the subsurface geology and extent of impacted soil. In November and December of 2002, BEII drilled seven additional borings (BSB-11 through BSB-17), pushed fifteen additional CPT locations (CPT-12 through CPT-26), and installed twelve additional monitoring wells (MW-10 through MW-21) to help further define the subsurface geology and the extent of VOC-impacted soil/groundwater. Monitoring well MW-1 was also abandoned. In late June of 2003, BEII installed five additional monitoring wells (MW-22 through MW-26) to help define the extent of VOC-impacted soil and groundwater. Monitoring wells MW-2, MW-3, and MW-7 were abandoned. Laboratory results were submitted by BEII to the DTSC. A *Summary Site Characterization Report*, dated February 2004, was submitted by Shaw Environmental & Infrastructure, Inc. (Shaw) to the DTSC and included interpretations based on the above-mentioned borings, CPT locations, and monitoring wells. See Figure 2 for Site Layout Map.

4.0 REGIONAL GEOLOGY/HYDROGEOLOGY

The site is located near the northern boundary of the Santa Fe Springs Plain within the Los Angeles Coastal Plain at an elevation of approximately 150 feet above mean sea level (msl). Surface sediments consist of fluvial deposits composed of interbedded gravel, sand, silt, and clay. Available data from California Water Resources Bulletin No. 104 (June 1961) indicate that the surface sediments may be Holocene and/or part of the upper Pleistocene Lakewood Formation, which ranges from 40- to 50 feet thick beneath the site. The Lakewood Formation has lateral lithologic changes with discontinuous permeable zones that vary in particle size. Stratified deposits of sand, silty sand, silt, and fine-grained gravel comprising the upper portion of the lower Pleistocene San Pedro Formation underlies the Lakewood Formation.

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 4**

The site lies within the Central Basin Pressure area, a division of the Central Ground Water Basin, which extends over most of the Coastal Plain. The shallow (perched) groundwater occurs within the Lakewood Formation. The deeper groundwater occurs in the Hollydale aquifer, which is the uppermost regional aquifer in the Pleistocene San Pedro Formation. The major water-producing aquifers in the region are the Lynwood aquifer located approximately 200 feet bgs, the Silverado aquifer located at approximately 275 feet bgs, and the Sunnyside aquifer located at approximately 600 feet bgs.

5.0 SITE GEOLOGY/HYDROGEOLOGY

Based on the borings and CPT pushes, Shaw identified six distinct hydrostratigraphic units beneath the ACC site. Uppermost is an "overburden" unit comprised of a wide range of materials from fill to silty sands to clayey silts that is designated as "unit A". Next is a well-defined, clean sand (sometimes with gravel) unit designated as "unit B". Following is a fine-grained, predominantly silt zone designated as "unit C1" which is underlain by a coarser-grained, silty sand zone named "unit D". Next is the finest-grained unit observed, "unit C2", which is predominantly a clayey silt that can be finer-grained (clay) at the top and coarser-grained (sandy silt) with depth. Finally, "unit E" is a clean, coarse-grained sand (similar to unit B) that is considered the top of the regional aquifer system.

A perched water zone, which is currently dry, was identified within unit B. The regional aquifer zone from 50- to 80 feet bgs (referred as the A1 zone), is identified within unit E. A zone of saturation (referred as the "first water" zone) exists between the A1 and the perched water zone.

For this report, monitoring wells MW-13, -14, -15, -17, -20, and -21 will be referred to as 'upper A1 zone monitoring wells' and MW-23, -24, and -25 as 'lower A1 zone monitoring wells'. Monitoring wells MW-4, -6, -8, -9, -10, -11, -12, -16, -18, -19, -22, and -26 will be noted as the 'first water zone monitoring wells'. Monitoring wells MW-4, MW-6, and MW-22 had insufficient water for collection during this sampling event.

The groundwater gradient has historically been to the southwest, as interpreted by SCS. In December 2005, the first water was measured to be at depths between 26.59- and 39.88 feet bgs. A potentiometric groundwater contour map of the first water is included as Figure 3. Groundwater in the A1 zone was measured to be at depths between 37.65- and 42.44 feet bgs. A potentiometric groundwater contour map of the upper A1 zone water is included as Figure 4. Depths to groundwater and their respective elevations are presented in Table 1.

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 5**

Hydrographs are included as Figures 5 through 8 in this report. Groundwater elevations of both the first water and A1 zone tend to be higher in June and lower in December, which suggests a seasonal recharge in both hydrologic zones. Groundwater levels generally declined from June 2003 to December 2004, interpreted as being due to limited rainfall, which supplies seasonal recharge. The most recent groundwater elevations measured in December 2005 ~~coincide with~~ reflect seasonal changes ~~with~~ manifest in decreased ~~in~~ groundwater elevations in all A1 zone wells and ~~an~~ increased groundwater elevations in first water wells (except for wells MW-9, -16, -22, and -26, which all show a decrease).

6.0 GROUNDWATER MONITORING PROTOCOL

The purpose of the current groundwater monitoring program is to provide data to the DTSC regarding the piezometric surface, water quality, and the presence of free product (FP), if any, on a quarterly basis. Groundwater monitoring consists of such activities as water level measurement, well sounding for detection of FP, collection of groundwater samples, field analysis, laboratory analysis, and reporting. The field work was performed as follows.

The depth to groundwater was measured in each well using a decontaminated water-level indicator capable of a measurement to within 1/100th of a foot. Prior to, and following, collection of measurements from each well, the portion of the water-level indicator entering groundwater was decontaminated using a 3-stage decontamination procedure consisting of a potable wash with water containing Liquinox soap followed by a double-purified water rinse. The depth to water was measured in all monitoring wells before any of the wells were purged. Wells were measured in the order of least- to the most contaminated based on past analyses. For the FACC wells, the following order of wells was followed: MW-23, -24, -25, -20, -17, -13, -14, -15, -12, -22, -9, -26, -11, -8, -21, -16, -10, -4, -6, -18, and -19.

The well-box and casing were opened carefully to preclude debris or dirt from falling into the open casing. Once the well-cap was removed, the water-level indicator was lowered into the well until a consistent tone was registered. Several soundings were repeated to verify the measured depth to groundwater. The depth of groundwater was measured from a reference point marked on the lip of each well casing. A licensed surveyor has surveyed the elevation of each reference point. The depth of groundwater was recorded on the field sampling log for each well. Other relevant information such as physical condition of the well, presence of hydrocarbon odors, etc. was also recorded as appropriate on the field sampling log.

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 6**

The well sounder used for this project was equipped to measure free-product (FP) layers thicker than 0.1 inches. FP was is defined for this site identified as 'light non-aqueous phase liquid' (LNAPL) or 'dense non-aqueous phase liquid' (DNAPL).

Groundwater purging was conducted immediately following the sounding of all monitoring wells. Groundwater samples were analyzed for the following constituents (new wells for Total Petroleum Hydrocarbons as gasoline (TPH-gas) and Volatile organic compounds (VOCs) only):

- VOCs using EPA Method 8260B to include all Tentatively Identified Compounds (TICs).
- TPH-gas using EPA Method 8015 modified.
- Total dissolved solids (TDS) using EPA Method 160.1.
- Nitrates, chloride, sulfate, sulfide, ferrous iron, and manganese using EPA Methods 352.1, 325.3, 375.4, 376.1, 7380, and 7460, respectively.
- Alkalinity, carbonates, and bicarbonates using EPA Methods 310.1 and Standard Method 4500.
- Total organic carbon (TOC) and dissolved organic carbon (DOC) using EPA Method 415.1, and 9060.
- 1,4-Dioxane using EPA method 8270 (MW-8, -10, -12, -13, -17, -20).
- Ethylene using GC/FID.

6.1 Well Purging and Measurement of Field Parameters

Wells were purged in the above-mentioned order (see Section 5.0) to minimize the potential for cross-contamination. One equipment blank was collected daily to assess whether cross-contamination had occurred. The wells were purged by Blaine Tech Services, Inc. (Blaine) and sampled by CSI on June 3, 2005. Snap Samplers™ were removed on the same day. The purge protocol is presented in the Field Sampling Plan (Appendix A) submitted to the DTSC in *Groundwater Monitoring Work Plan* (dated October 23, 2001).

Prior to purging, casing volumes were calculated based on total well depth, static water level, and casing diameter. One casing volume was calculated as:

$$V = \pi(d/2)^2 h \times 7.48$$

Where:

V is the volume of one well casing of water (in gallons, 1 ft³ = 7.48 gallon);

d is the inner diameter of the well casing (in feet); and

h is the total depth of water in the well - the depth to water level (in feet).

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 7**

A minimum of three casing volumes of water was purged from each well, except when the well was dewatered. Water was collected into a measured bucket to record the purge volume. All purged groundwater was containerized in 55-gallon hazardous waste drums for disposal at a later date. Well MW-26 was not purged due to insufficient water.

The pump was initially set at approximately 2 feet below the measured groundwater level in each well. The pump was lowered slowly as the groundwater receded. This ensured that fresh formation water was sampled from each well. Great care was used when deploying the pump to avoid touching the bottom of the well and when initiating the pump to minimize sediment disturbances from purging within the well. A low pump rate of 1 gallon per minute (gpm) or less was used to prevent dewatering. Monitoring wells MW-8 and MW-10 dewatered during this sampling event.

After each well casing volume was purged; water temperature, pH, specific conductance (EC), and turbidity were measured using field test meters and the measurements were recorded on Well Monitoring Data Sheets (See Appendix A). Samples were collected after these parameters have stabilized; indicating that representative formation water has entered the well. The temperature, pH, and specific conductance should not vary by more than 10 percent from reading to reading. Turbidity should be less than 5 NTUs, however, the purging process stirred up silty material in each well which made the turbidity measurements of 5 NTUs unattainable. Groundwater samples were collected after water levels recharged to 80 percent of the static water level. Notations of water quality including color, clarity, odors, sediment, etc. were also noted in the data sheets.

All field meters were calibrated according to manufacturers' guidelines and specifications before and after each day of field use. Field meter probes were decontaminated before and after use at each well. The pH, conductivity, D.O., ORP, and temperature were measured with a YSI 556 and turbidity was measured with a HF Scientific DRT-15C meter. The calibration standards used for pH were 4, 7 and 9 with expiration dates of June 2006. Conductivity was calibrated to a 3900 μs standard which did not have an expiration date. A 0.02 NTU standard was used to calibrate the turbidity and did not have an expiration date.

6.2 Well Sampling

Groundwater samples were collected using two methods: disposable bailers and Snap Samplers™. Monitoring wells MW-8, -9, -10, -11, -12, -13, -14, -15, -16, -17, -20, -22 and -26 were sampled by lowering a separate disposable bailer into each well. Groundwater was transferred from the bailer directly into the appropriate sample containers with preservative, if required, chilled, and processed for shipment to the laboratory. When transferring samples, care was taken not to touch the bailer-emptying

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 8**

device to the sample containers. Snap Samplers™ were used to collect samples from MW-23, -24 and -25. Water samples were transported to Southland Technical Services, Inc., a certified laboratory by the California Department of Health Services (Cert. #1986), to perform the requested analysis.

Groundwater samples were collected in the following order: MW-20, -13, -17, -15, -14, -12, -26, -11, -9, -10, -16, -8, -23, -24, and -25. Monitoring wells MW-4, -6, and -22 had insufficient water for sampling.

The Snap Sampler™ is a groundwater sampling device that employs a double-opening 40 ml VOA vial. The vial seals under the water surface using a remote trigger. The trigger releases an internal, PFA Teflon-coated, stainless steel spring that seals PTFE or PFA Teflon end-caps onto the bottle. The end-caps are designed to seal the water sample within the VOA vial with no headspace vapor. Once the closed vial is retrieved from the well, the bottle is prepared with standard septa screw caps and a label. All critical actions take place submerged in the well, away from weather, surface contamination, and off-gassing loss. The vial can be used directly in standard laboratory autosampler equipment. The sample is never exposed to the open air from the well to the gas chromatograph. Analytical results for the Snap Samplers™ are included in Appendix B.

Monitoring wells MW-18 and MW-19 identified FP as LNAPL at a thickness of <0.01feet. MW-21 initially yielded no sheen or product, but sheen was present in the well after purging.

Vials for VOC and TPH analysis were filled first to minimize aeration of groundwater collected in the bailer. The laboratory provided vials containing sufficient HCl preservative to lower the pH to less than 2. The vials were filled directly from the bottom-emptying device. The vial was capped with a cap containing a Teflon septum. A blind duplicate sample for the laboratory was labeled as "MW-1" and was collected from monitoring well MW-11. Equipment blanks were collected every day. EB-1 was collected after purging MW-8. All vials were inverted and tapped to check for bubbles to insure zero headspace.

New nitrile gloves were worn during by sampling personnel for each well to prevent cross-contamination of the samples. A solvent-free label was affixed to each sample container/vial denoting the well identification, date and time of sampling, and an identifying code to distinguish each individual bottle.

6.3 Sample Handling

VOA vials, including laboratory trip blanks, were placed inside of one new Ziplock bag per well and stored in a cooler chilled to approximately 4°C with bagged ice.

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 9**

Water samples were logged on the chain-of-custody forms immediately following sampling of each well to insure proper tracking through analysis to the laboratory.

6.4 Waste Management

Free product (FP), purged groundwater, and decontamination water were stored in sealed 55-gallon drums for a period not to exceed 90 days. Stored wastes will be profiled for hazardous constituents and characterized as Non-Hazardous, California Hazardous, or RCRA Hazardous, as appropriate. Any transportation of waste will be under appropriate manifest.

7.0 FREE PRODUCT

FP was identified as LNAPL in monitoring wells MW-18 and MW-19 at thicknesses of 0.01- and 0.12-feet, respectively. Each well that contains or has contained FP is tabulated as follows with the total amount of FP removed since each well was installed.

<u>Well ID</u>	<u>Total FP Removed (liters)</u>
• MW-4	0.04
• MW-6	15.165
• MW-8	26.49
• MW-10	14.751
• MW-16	0.93
• MW-18	208.022
• MW-19	40.923
• MW-21	1.558
TOTAL	307.879

Laboratory analysis of FP was performed in October 2001 from MW-6, in June 2002 from MW-6 and MW-8, in December 2003 from MW-16 and MW-19, in March 2004 from MW-10, MW-18 and MW-19, and in September 2004 from MW-8, MW-10, and MW-19. Laboratory analysis results are presented in Table 2. Based on the results, the FP contained in MW-6 and MW-8 appears to be different from the FP contained in MW-10, MW-16, and MW-19 when comparing TPH-gas concentrations. Furthermore, the VOC analysis results indicate that FP from MW-10 and MW-18 were similar as compared to the FP from MW-19.

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 10**

8.0 GROUNDWATER SAMPLE RESULTS

Groundwater samples collected from the first water zone monitoring wells MW-8, -9, -10, -11, -12, -16, and -26 in December 2005 contained dissolved TPH-gas at 64,600; 3,600; 87,100; 238,000; 1,470; 21,800; and 158,000 µg/L, respectively. See Table 3 and Figure 9 for dissolved TPH-gas concentrations. Graphs of dissolved contaminant concentrations over time are provided in Appendix B. Note that the previously high dissolved TPH-gas concentration from MW-11 has dropped by over 75%.

Groundwater samples collected from the upper A1 zone monitoring wells MW-13, -14, 15, -17, and -20 in December 2005 contained TPH-gas ranging from 81.5 µg/L in MW-20 to 885 µg/L in MW-15. The lower A1 zone monitoring wells MW-23, -24, and -25 showed dissolved TPH-gas as 288; 341; and 165 µg/L, respectively. See Table 3 and Figure 10 for dissolved TPH-gas concentrations. Generally, contaminant graphs for the A1 zone show a slight increase in dissolved TPH-gas concentrations in most wells during the month of September, except for MW-14 which shows a decreased concentration.

Concentrations of dissolved BTEX in the first water zone ranged from 24,797 µg/L in MW-26 to 19 µg/L in MW-12 (See Table 4 and Figure 9 for dissolved BTEX concentrations). Most of the total dissolved BTEX concentrations consist of toluene. Contaminant graphs for benzene and toluene are provided in Appendix B.

Dissolved BTEX in the upper A1 zone ranged between 92.5 µg/L in MW-15 to <5 µg/L in MW-13, -14, and -17 (See Tables 4 and 5 and Figure 10 for dissolved BTEX concentrations). Like the first water zone, the upper A1 zone contains mostly toluene as the total dissolved BTEX concentration. Contaminant graphs for benzene and toluene showed lower concentrations in most wells during the months of June and December. Maximum concentrations are identified in monitoring well MW-15 in June 2005 and MW-14 in September 2005. The lower A1 zone monitoring wells MW-23, -24, and -25 identified no detectable concentrations of dissolved BTEX.

Groundwater sample results from the first water zone identified high VOC concentrations as compared to the relatively low VOC concentrations in the A1 zone (See Tables 4 and 5).

Dissolved PCE was identified in the first water zone at a maximum concentration of 1,080 µg/L from MW-26. Dissolved TCE was identified at a maximum of 2,160 µg/L from MW-26 in the first water zone (See Figure 11). Dissolved contaminant graphs identified relatively consistent dissolved PCE and TCE concentrations from first water wells except for MW-26, where concentrations fluctuate greatly. Maximum concentrations of dissolved PCE and TCE in the upper A1 zone were determined to be 36.3 µg/L in MW-17 and 28.9 µg/L in MW-13, respectively (See Figure 12). The lower

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 11**

A1 zone contained maximum concentrations of dissolved PCE (142 µg/L in MW-23) and TCE (86 µg/L in MW-24). Wells in the upper and lower A1 zones exhibited a general increase in dissolved PCE and a decrease in dissolved TCE (See Appendix B).

Dissolved concentrations of 1,1,1-TCA in the first water zone were determined to be a maximum of 4,710 µg/L in MW-26 (See Figure 11). Contaminant graphs for the first water showed that in most wells with elevated dissolved 1,1,1-TCA (>100 µg/L) the maximum concentrations were detected during the month of December 2002 and most wells with low level dissolved 1,1,1-TCA (<100 µg/L) the maximum concentrations were detected in June 2003. Dissolved 1,1,1-TCA was not detected or "ND" (<4 µg/L in MW-14, <20 in MW-9 and <2 µg/L in any of the other wells) in the A1 zone (See Figure 12), except for MW-20 (2.2 µg/L). Graphs of dissolved 1,1,1-TCA over time in the A1 zone illustrate that June 2004 was the first date where concentrations were all below 14 µg/L. Only MW-21 and MW-23 have had concentrations above that level in September 2004 and December 2005, respectively.

Groundwater samples were also analyzed for 1,4-Dioxane, a preservative used in 1,1,1-TCA to prolong its shelf life. However, 1,4-Dioxane is more soluble in groundwater than 1,1,1-TCA and will often lead the dissolved 1,1,1-TCA plume. First water zone monitoring wells identified dissolved 1,4-Dioxane concentrations between 24,100 µg/L and <2 µg/L. A1 zone monitoring identified dissolved 1,4-Dioxane concentrations between 96.5 µg/L and <2 µg/L. Dissolved concentrations in most wells decreased over time until March 2005 when concentrations began increasing in MW-9, -14, and -16 (See Appendix B).

Concentrations of dissolved chlorinated VOC daughter products were relatively elevated compared to their respective parent VOCs identified above and also showed a trend of higher dissolved concentrations in the first water zone compared to the deeper A1 zone.

1,1-DCA is a daughter product from reductive dehalogenation of 1,1,1-TCA and from carbon-carbon double-of 1,1-DCE, another daughter product. Dissolved 1,1-DCA concentrations were identified between 34,100 µg/L and 20.5 µg/L in the first water zone (See Figure 11). The greatest dissolved 1,1-DCA concentration was observed in MW-11. An historic maximum concentration was identified in MW-11 during December 2004 (See Appendix B). Dissolved 1,1-DCA concentrations in the upper A1 zone ranged between 262 µg/L and <1 µg/L (See Figure 12). Dissolved 1,1-DCA concentrations identified in the lower A1 zone were between 51.5 µg/L and <1 µg/L. Most wells in the A1 zone identified exhibited a slight increase or stable levels of dissolved 1,1-DCA concentrations since the previous event.

Dissolved 1,1-DCE, a daughter product of the dehydrohalogenation of 1,1,1-TCA and reductive dehalogenation of TCE, was identified at concentrations ranging from

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 12**

9,210 µg/L to <2 µg/L in the first water zone (See Figure 11). The maximum dissolved 1,1-DCE concentration was observed in MW-26. Historically, dissolved concentrations of 1,1-DCE fluctuate with no observable pattern (See Appendix B). Dissolved 1,1-DCE concentrations in the upper A1 zone ranged between 262 µg/L and 11.3 µg/L (See Figure 12). Concentrations of detected dissolved 1,1-DCE were identified at a maximum of 636 µg/L in the lower A1 zone from MW-23. The A1 zone identified showed overall elevated dissolved 1,1-DCE concentrations in December 2005.

Cis-1,2 DCE is also a daughter product of the dehydrohalogenation of 1,1,1-TCA and reductive dehalogenation of TCE. Concentrations of dissolved cis-1,2-DCE were identified between 10,600 µg/L (in MW-26) and 4.4 µg/L in the first water zone (See Figure 11). Historically, dissolved concentrations of cis-1,2-DCE fluctuate with no observable pattern (See Appendix B). Dissolved cis-1,2-DCE concentrations in the upper A1 zone ranged from 3 µg/L to a maximum of 265 µg/L identified from MW-15 (See Figure 12). The lower A1 zone contained dissolved cis-1,2-DCE at a maximum of 24.9 µg/L from MW-23. Contaminant graphs from the A1 zone show a general decrease in dissolved cis-1,2-DCE over time with the exceptions of MW-15, -16, -21, and -26. MW-21 showed elevated concentrations (<2,500 µg/L) in March and September 2004 and MW-15 showed elevated concentrations in March 2004, and again in March and June 2005.

Vinyl chloride (VC) is a by-product from the dehydrohalogenation and reductive dehalogenation of the chlorinated VOC daughter products mentioned above. Similar to the other VOCs, concentrations of dissolved VC were at lower concentrations in the deeper A1 zone than in the first water zone. Dissolved VC concentrations were identified between 4,050 µg/L (in MW-8) and 4.4 µg/L in the first water zone (See Figure 11). An increase in VC in the first water zone was observed over time in MW-11 (See Appendix B). Dissolved VC concentrations in the upper A1 zone ranged from 721 µg/L to <1 µg/L (See Figure 12). Dissolved VC was ND in the lower A1 zone. The A1 zone wells showed fluctuations of dissolved VC concentrations with no discernable pattern.

Dissolved methylene chloride was identified in the first water zone at concentrations between 10,000 µg/L (in MW-26) and <2 µg/L (See Figure 11). Methylene chloride was ND (<4 in MW-14 and <2 µg/L in all other wells) in the upper and lower A1 zone monitoring wells sampled (See Figure 12).

Dissolved acetone was identified in first water zone monitoring well MW-26 at a concentration of 9,440 µg/L. Dissolved MEK concentrations ranged from 4,120 µg/L (in MW-26) to <5 µg/L in first water wells (See Figure 13). No detectable concentrations of acetone or MEK were identified above method detection limits in either the upper or lower A1 zones (See Figure 14). Historically, dissolved concentrations of acetone and MEK fluctuate with no observable pattern (See Appendix B).

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 13**

Detectable concentrations of dissolved MIBK were identified between 7,120 µg/L to <5 µg/L in the first water wells sampled this quarter (See Figure 13). No detectable concentrations were identified in any upper and lower A1 zone monitoring wells sampled (See Figure 14).

Most groundwater samples were also analyzed for biodegradation indicators (See Table 6 for laboratory results). The combination of elevated daughter products with elevated oxygen levels (>0.5 mg/L O₂) indicates that aerobic biodegradation is a dominant electron-accepting process in MW-10, -13, -14, -20, -22, and -26. Lower oxygen levels and higher nitrate levels in MW-9, -11, -12, and -15 suggest that nitrate reduction is a principal electron-accepting process in these wells. MW-17 and -20 have elevated DO and nitrate.

All groundwater laboratory analytical reports for this quarterly groundwater monitoring episode are included as Appendix C.

9.0 VOCS CAPTURED AND TREATED BY THE SVE SYSTEM

During the 4th quarter 2005 Clean Soils, Inc. began VOC treatment of the vadose zone at the ACC site¹. VOC vapor concentrations collected periodically by CSI from gases entering the SVE system were used to estimate the volume of VOCs extracted from the vadose zone.

From the startup of the VOC system on October 20, 2005 through December 31, 2005, the unit operated a total of 73 days with an average of 19.0 hours per day of run time. During this period, the SVE system averaged a flow rate of 247 scfm with VOC vapor concentrations averaging 750.5 ppmv, as measured with a PID. The SVE system was up and operating an average of 79% of the time during this period.

Based on an average molecular weight of 138 pounds per pound mole for the VOC vapor, the SVE system removed and treated 5,095.4 pounds during the 4th quarter, 2005. The formula and the basis of the values used in the formula to calculate the amount of VOCs removed and treated are present in Tables 7 – 9.

10.0 CONCLUSIONS

Based on groundwater elevation data, it is conclude that seasonal changes affect both the first water and A1 zones. In general, both groundwater zones observed a period of discharge during winter and recharge during summer months.

¹ Estimated volumes of VOCs extracted and treated by the SVE system will be included as part of the quarterly groundwater monitoring reports being submitted to the Department of Toxics Substances Control

**Former Angeles Chemical Co.
2005 Fourth Quarter
Groundwater Monitoring Report
Page 14**

Based on the recent groundwater sample results, it is concluded that the site is impacted by LNAPL in the first water and upper A1 zones and dissolved VOCs in both the first water and A1 zones. LNAPL was identified in two first water monitoring wells (MW-18 and MW-19) and as a sheen in upper A1 zone well MW-21. Elevated dissolved phase VOCs were identified in first water monitoring wells MW-8, -9, -10, -11, -16, -22, and -26. Dissolved VOC concentrations, however, were detected at higher concentrations in the first water zone by an order of magnitude as compared to the A1 zone ~~by an order of magnitude~~.



Another conclusion is that the recent groundwater sampling data provide preliminary support that the site has potential for intrinsic biodegradation. Dissolved parent VOC (PCE, TCE, and 1,1,1-TCA) concentrations were identified at concentrations less than 500 µg/L, except in MW-10 and MW-26 where concentrations were above 500 µg/L but were lower than the June 2005 concentrations. Daughter VOC constituents such as 1,1-DCA, 1,1-DCE, cis-1,2-DCE, and VC were detected at dissolved concentrations of up to 34,100 µg/L. The low parent VOC concentration to high daughter VOC concentration ratio is a preliminary indicator of intrinsic biodegradation.

11.0 RECOMMENDATIONS

The following recommendations are offered::

- Continued quarterly groundwater monitoring for VOCs and TPH-gas;
- Continued free product removal on a monthly basis;
- Continued Soil Vapor extraction (operations began in October 2005) and monitoring.

FIGURES



Legend
8915 Sorensen Ave.

Clean Soil, Inc.
 4359 Phelan Road
 Phelan, CA 92371

Site Location Map
 Former Angeles Chemical Company
 8915 Sorensen Ave., Santa Fe Springs, CA 90670

**FIGURE
 1**


FIGURE 2

MONITORING WELL LOCATIONS

FORMER ANGELES CHEMICAL CO.
8915 SORENSEN AVENUE, SANTA FE SPRINGS, CA 90670


Legend

●	MONITORING WELL
◆	BORING LOCATION
■	CPT LOCATION
○	TANK
▪	DRAIN
■■■	RAILING TRACKS
—	CHAIN LINK FENCE
—	TOP OF CASING
—	TOP OF RIM
—	FLASH SURFACE







































































































GRAPHIC SCALE

50 0 25 50
FEET




GRAPHIC SCALE

50 0 25 50
FEET



Legend	
Railroad Tracks	
Chain Link Fence	
• Monitoring Well	
1/16.00 ft²	



feet
0 25 50

Legend

- Railroad Tracks
- Chain Link Fence
- Monitoring Well
- Approximate 3000'




Figure 5: First Water Groundwater Elevations from Central and Northern Wells




Figure 7: Upper A1 Groundwater Elevations




Figure 6: First Water Groundwater Elevations from Southern Wells






Figure 8: Lower A1 Groundwater Elevations








Prepared by
Clean Soil, Inc.
4359 Phelan Road, Phelan, CA 92371


TPH-gas and BTEX Concentrations in First Water (µg/L)
Former Angeles Chemical Company, 8915 Sorensen Ave., Santa Fe Springs, CA 90670

FIGURE
9









DATES OF SURVEY

DECEMBER 18, 2002
MAY 17, 2003
JULY 25, 2003


Prepared by:

Clean Soil, Inc.
4359 Phelan Road, Phelan, CA 92371

Acetone, MEK and MIBK Concentrations in First Water ($\mu\text{g/L}$)

Former Angeles Chemical Company, 8915 Sorensen Ave., Santa Fe Springs, CA 90670

**FIGURE
13**



TABLES

Table 1: Well and Screen Elevations and Groundwater Depths to Water and Elevation (in feet)

Table 1: Well and Structure Elevations and Groundwater Depths to Water and Elevations (in feet)																												
Date	MW-1			MW-2			MW-3			MW-4			MW-5			MW-6			MW-7			MW-8			MW-9			
	NA	150.42	150.78	149.27	149.58	148.62	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44	149.12	149.44		
Groundwater Elevation (TOC)	40'-60'	30'-50'	25'-40'	17'-27'	20'-30'	34'-55'	30.5-45.5'	25'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'		
Structural Interval (deg)	40'-60'	30'-50'	25'-40'	17'-27'	20'-30'	34'-55'	30.5-45.5'	25'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'	30'-40'		
Structural Elevation	Top	NA	120.42	121.78	121.27	119.78	114.82	119.13	119.66	124.41	119.12	120.09	98.22	95.86	98.65	103.63	148.32	150.66	148.32	148.32	148.32	148.32	148.32	148.32	148.32	148.32	148.32	
	Bottom	NA	100.42	101.78	101.27	100.78	93.62	101.13	103.98	106.41	109.12	110.09	89.22	95.66	96.85	103.63	104.2	110.67	120.67	110.67	110.67	110.67	110.67	110.67	110.67	110.67	110.67	110.67
Depth to Water (ft)	Feb-04	30.03	28.0	28.7	23.85	24.85	24.53	28.0	28.7	30.03	30.07	30.11	30.98	34.7	32.88	34.11	33.62	34.67	33.28	41.66	43.06	43.63	33.69	40.44	33.33	41.11	42.34	
	Nov-00	35.62'	35.25'	36.42'	26.2	26.52'	26.19'	28.7	NA	26.85	NA	26.85	NA	26.85	NA	26.85	NA	31.44	32.49	33.07	30.77	30.95	31.58	31.42	31.58	40.55		
	Oct-01	37.41'	37.91'	39.19'	26.55	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	30.15	31.05	31.85	32.01	32.61	33.29	33.23	33.29	33.22	33.22	
	Nov-01	34.16	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	31.15	31.88	31.84	43.19	43.79	40.65	41.55	41.55	41.55	41.55	
	Feb-02	36.2	36.19	37.38	26.44	30.32	28.21	20	20	19	21	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	
	Jun-02	38.75	38.19	38.19	26.48	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	30.07	30.11	30.11	30.11	30.11	30.11	30.11	30.11	30.11	30.11	
	Oct-02	42.45'	43.68'	44.98'	44.98	26.48	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	32.71	33.28	33.28	33.28	33.28	33.28	33.28	33.28	33.28	33.28	
	Dec-02	NA	43.19	44.22	26.26	FP orth	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	33.63	34.67	34.67	43.66	43.66	43.66	43.66	43.66	43.66	43.66	
	Feb-03	NA	41.07'	41.35'	26.36	FP orth	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	31.44	32.49	32.49	30.77	30.77	30.77	30.77	30.77	30.77	30.77	
	Jun-03	NA	39.68	39.88	26.35	FP orth	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	30.15	31.15	31.05	37.85	37.85	37.85	37.85	37.85	37.85	37.85	
	Aug-03	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	32.34	32.34	44.16	44.16	44.16	44.16	44.16	44.16	44.16	44.16	
	Dec-03	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	34.15	35.96	35.96	43.85	43.85	43.85	43.85	43.85	43.85	43.85	
	Feb-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	35.2	36.19	36.19	45.12	45.12	45.12	45.12	45.12	45.12	45.12	
	Mar-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	36.12	37.98	37.98	46.81	46.81	46.81	46.81	46.81	46.81	46.81	
	Jun-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	39.15	39.53	39.53	48.27	48.27	48.27	48.27	48.27	48.27	48.27	
	Aug-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	40.15	36.53	36.53	51.96	51.96	51.96	51.96	51.96	51.96	51.96	
	Dec-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	41.62	41.69	41.69	51.16	51.16	51.16	51.16	51.16	51.16	51.16	
	Feb-05	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	42.82	31.21	31.21	47.98	47.98	47.98	47.98	47.98	47.98	47.98	
	Jun-05	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	43.82	31.45	31.45	48.56	48.56	48.56	48.56	48.56	48.56	48.56	
	Aug-05	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	44.82	31.67	31.67	49.57	49.57	49.57	49.57	49.57	49.57	49.57	
	Dec-05	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	45.82	31.91	31.91	50.55	50.55	50.55	50.55	50.55	50.55	50.55	
	Feb-06	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	46.82	32.15	32.15	51.59	51.59	51.59	51.59	51.59	51.59	51.59	
	Jun-06	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	47.82	32.38	32.38	52.56	52.56	52.56	52.56	52.56	52.56	52.56	
	Aug-06	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	48.82	32.61	32.61	53.53	53.53	53.53	53.53	53.53	53.53	53.53	
	Dec-06	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	49.82	32.74	32.74	54.50	54.50	54.50	54.50	54.50	54.50	54.50	
	Feb-07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	50.82	32.87	32.87	55.47	55.47	55.47	55.47	55.47	55.47	55.47	
	Jun-07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	51.82	33.00	33.00	56.42	56.42	56.42	56.42	56.42	56.42	56.42	
	Aug-07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	52.82	33.13	33.13	57.37	57.37	57.37	57.37	57.37	57.37	57.37	
	Dec-07	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	53.82	33.26	33.26	58.32	58.32	58.32	58.32	58.32	58.32	58.32	
	Feb-08	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	54.82	33.39	33.39	59.27	59.27	59.27	59.27	59.27	59.27	59.27	
	Jun-08	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	55.82	33.52	33.52	60.22	60.22	60.22	60.22	60.22	60.22	60.22	
	Aug-08	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	56.82	33.65	33.65	61.17	61.17	61.17	61.17	61.17	61.17	61.17	
	Dec-08	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	57.82	33.78	33.78	62.12	62.12	62.12	62.12	62.12	62.12	62.12	
	Feb-09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	58.82	33.91	33.91	63.07	63.07	63.07	63.07	63.07	63.07	63.07	
	Jun-09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	59.82	34.04	34.04	63.92	63.92	63.92	63.92	63.92	63.92	63.92	
	Aug-09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	60.82	34.17	34.17	64.87	64.87	64.87	64.87	64.87	64.87	64.87	
	Dec-09	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	61.82	34.30	34.30	65.82	65.82	65.82	65.82	65.82	65.82	65.82	
	Feb-10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	62.82	34.43	34.43	66.82	66.82	66.82	66.82	66.82	66.82	66.82	
	Jun-10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	63.82	34.56	34.56	67.82	67.82	67.82	67.82	67.82	67.82	67.82	
	Aug-10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	64.82	34.69	34.69	68.82	68.82	68.82	68.82	68.82	68.82	68.82	
	Dec-10	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	65.82	34.82	34.82	69.82	69.82	69.82	69.82	69.82	69.82	69.82	
	Feb-11	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	66.82	34.95	34.95	70.82	70.82	70.82	70.82	70.82	70.82	70.82	
	Jun-11	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	67.82	35.08	35.08	71.82	71.82	71.82	71.82	71.82	71.82	71.82	
	Aug-11	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	68.82	35.21	35.21	72.82	72.82	72.82	72.82	72.82	72.82	72.82	
	Dec-11	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	69.82	35.34	35.34	73.82	73.82	73.82	73.82	73.82	73.82	73.82	
	Feb-12	NA	NA																									

Table 2: TPH-gas and VOCs from Free Product Sample Results using EPA Methods 8015 and 8260µg/L)

	Date	MW-6	MW-8	MW-10	MW-16	MW-18	MW-19
Screened Interval (feet bg)		20-30	30.5-40.5	25-40	29-46	21-46	30-45
TPH-gas	Jun-02	8.E+08	8.E+08	NA	NA	NA	NA
	Dec-03	NA	NA	NA	4.55E+08	NA	4.25E+08
	Mar-04	NA	NA	446000	NA	NA	NA
VOCs							
Acetone	Oct-01	<25,000*					
	Mar-04	NA	NA	<1,250,000	NA	<1,250,000	<1,250,000
	Sep-04	NA	<2,500,000	<2,500,000	NA	NA	<2,500,000
Benzene	Oct-01	110,000*					
	Mar-04	NA	NA	<250,000	NA	<250,000	365,000
	Sep-04	NA	<100,000	<100,000	NA	NA	464,000
2-Butanone (MEK)	Oct-01	<25,000*					
	Mar-04	NA	NA	<1,250,000	NA	<1,250,000	<1,250,000
	Sep-04	NA	<2,500,000	<2,500,000	NA	NA	<2,500,000
Chloroethane	Mar-04	NA	NA	<500,000	NA	<500,000	<500,000
	Sep-04	NA	<200,000	<200,000	NA	NA	<200,000
1,1-Dichloroethane	Oct-01	592,000*					
	Mar-04	NA	NA	3,190,000	NA	1,590,000	625,000
	Sep-04	NA	4,040,000	5,740,000	NA	NA	1,326,000
1,2-Dichloroethane	Oct-01	<5,000*					
	Mar-04	NA	NA	<500,000	NA	<500,000	<500,000
	Sep-04	NA	<200,000	<200,000	NA	NA	<200,000
1,1-Dichloroethene	Oct-01	417,000*					
	Mar-04	NA	NA	730,000	NA	928,000	4,840,000
	Sep-04	NA	782,000	710,000	NA	NA	5,860,000
cis 1,2-Dichloroethene	Oct-01	1,080,000*					
	Mar-04	NA	NA	1,530,000	NA	1,620,000	1,630,000
	Sep-04	NA	1,765,000	1,900,000	NA	NA	2,793,000
trans 1,2-Dichloroethene	Oct-01	<5,000*					
	Mar-04	NA	NA	<500,000	NA	<500,000	<500,000
	Sep-04	NA	<200,000	<200,000	NA	NA	<200,000
1,4 Dioxane	Mar-04	NA	NA	<12,500,000	NA	<12,500,000	<12,500,000
	Sep-04	NA	<5,000,000	<5,000,000	NA	NA	<5,000,000
Ethylbenzene	Oct-01	4,320,000*					
	Mar-04	NA	NA	5,330,000	NS-FP	7,080,000	6,960,000
	Sep-04	NA	5,910,000	7,280,000	NA	NA	8,770,000

Table 2: TPH-gas and VOCs from Free Product Sample Results using EPA Methods 8015 and 8260µg/L)

VOCs	Date	MW-6	MW-8	MW-10	MW-16	MW-18	MW-19
Methylene Chloride	Oct-01	<5,000*					
	Mar-04	NA	NA	<500,000	NA	<500,000	<500,000
	Sep-04	NA	<200,000	<200,000	NA	NA	<200,000
4-Methyl-2-pentanone	Oct-01	<25,000*					
	Mar-04	NA	NA	<1,250,000	NA	<1,250,000	<1,250,000
	Sep-04	NA	<2,500,000	<2,500,000	NA	NA	<2,500,000
Naphthalene	Oct-01	1,680,000*					
	Mar-04	NA	NA	1,980,000	NA	1,620,000	4,120,000
	Sep-04	NA	3,260,000	2,890,000	NA	NA	6,000,000
n-Propylbenzene	Mar-04	NS-FP	NS-FP	2,820,000	NA	3,230,000	2,980,000
	Sep-04	NA	3,787,000	3,700,000	NA	NA	4,240,000
Tetrachloroethene	Oct-01	531,000*					
	Mar-04	NA	NA	<500,000	NA	543,000	4,820,000
	Sep-04	NA	<200,000	<200,000	NA	NA	2,870,000
1,1,1-Trichloroethane	Oct-01	28,100,000*					
	Mar-04	NA	NA	8,870,000	NA	4,140,000	36,000,000
	Sep-04	NA	5,460,000	7,330,000	NA	NA	45,700,000
Trichloroethene	Oct-01	753,000*					
	Mar-04	NA	NA	<500,000	NA	<500,000	560,000
	Sep-04	NA	<200,000	<200,000	NA	NA	300,000
1,2,4-Trimethylbenzene	Oct-01	22,100,000*					
	Mar-04	NA	NA	31,900,000	NA	30,600,000	45,400,000
	Sep-04	NA	43,400,000	37,000,000	NA	NA	60,100,000
1,3,5-Trimethylbenzene	Oct-01	5,400,000*					
	Mar-04	NA	NA	8,560,000	NA	9,020,000	9,480,000
	Sep-04	NA	11,746,000	10,100,000	NA	NA	13,500,000
Toluene	Oct-01	9,010,000*					
	Mar-04	NA	NA	8,620,000	NA	15,300,000	11,400,000
	Sep-04	NA	9,010,000	15,200,000	NA	NA	16,400,000
Vinyl Chloride	Oct-01	<5,000*					
	Mar-04	NA	NA	<500,000	NA	<500,000	<500,000
	Sep-04	NA	<100,000	<100,000	NA	NA	<100,000
Xylenes	Oct-01	10,370,000*					
	Mar-04	NA	NA	17,600,000	NA	22,500,000	16,000,000
	Sep-04	NA	21,400,000	26,300,000	NA	NA	22,100,000

NA= Not Analyzed.

Blue= Chemicals stored on-site.

Red= Transformation compounds.

Table 3: Conductivity, pH, and TPH-gas Groundwater Sample Results using EPA Method 8015 ($\mu\text{g/L}$)

	MW-1	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-16	MW-17	MW-18	MW-19	MW-20	MW-21	MW-22	MW-23	MW-24	MW-25	MW-26	
Screened Interval (ft)	40-60	30-50	29-49	17-27	20-30	34-55	30.5-40.5	30.5-45.5	25-40	30-40	30-40	52-62	55-65	54-64	29-46	56-66	21-46	30-45	57-67	53-63	30-40	71-81	57-77	71-81	30-40		
Conductivity	Dec-02	NA	2011	2065	NA	NA	2710	NA	2331	2871	2886	1572	1374	1866	1821	2106	1885	2515	5977	1807	1746						
	Mar-03	NA	2094	1974	NA	NA	2768	NA	2325	4382	3793	1492	1802	1913	1818	2011	1892	2643	5912	1823	1695						
	Jun-03	NA	1763	1881	NA	NA	2882	NA	2406	4439	3245	1182	1832	1871	1851	1931	1913	2802	8017	1788	1790	2500	1200	1300	1300	3000	
	Sep-03	NA	NA	NA	NA	NA	NA	NA	2540	3978	3580	1313	1904	2100	1949	2219	2530	3028	NS-FP	1868	1910	NS-NW	2285	1799	1883	NS-NW	
	Dec-03	NA	NA	NA	NA	NA	NA	NA	2585	2850	3070	1387	1953	1984	1827	NS-FP	1981	2674	NS-FP	2192	1868	NS-MW	NA	NA	NA	NS-NW	
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	2693	2582	1313	2080	1999	2073	NS-FP	1854	NS-FP	NS-FP	2166	2080	1663	NA	NA	NA	NA	2302	
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	2474	NS-FP	2502	1270	1812	1764	1826	NS-FP	1897	NS-FP	1779	1807	NA	1117	1507	1807	2032		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	2558	NS-FP	2374	1171	2014	1819	2032	NS-FP	1781	NS-FP	1897	1906	NA	NA	NA	NA	NA		
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	2075	1595	1016	1750	1725	1509	1663	NS-FP	1843	NS-FP	NS-NW	NA	NA	NA	NA	NA	NS-NW		
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	3398	4211	NS-FP	3857	1915	1744	2122	2981	1906	2170	NS-FP	1798	NS-FP	2528	NA	NA	NA	3679	
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	1575	2478	1595	2369	1226	1700	1885	1812	2118	1861	NS-FP	1888	1747	1505	NA	NA	NA	NA	2280
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	1579	2501	1457	1566	1168	1726	1840	1869	1977	1815	NS-FP	1862	1785	1426	NA	NA	NA	2192	
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	1966	2921	1670	1872	1175	1985	2223	2168	2362	2494	NS-FP	NS-FP	2298	NS-FP	NS-NW	NA	NA	NA	1996
pH	Dec-02	NA	6.83	6.82	NA	NA	6.75	NA	6.58	6.82	8.87	7.02	8.97	6.83	6.93	6.58	6.93	8.68	7.02	6.98	6.98						
	Mar-03	NA	6.6	6.9	NA	NA	6.7	NA	7	6.7	6.6	7.1	7.5	7	7.8	6.8	7.2	6.8	6.9	7.3	7.6						
	Jun-03	NA	6.8	6.7	NA	NA	6.6	NA	6.7	6.4	6.6	6.4	6.8	6.8	6.7	6.5	6.8	6.3	6.7	6.9	6.8	NA	NA	NA	NA	NA	
	Sep-03	NA	NA	NA	NA	NA	NA	NA	6.61	6.55	6.52	6.49	6.93	6.9	6.75	6.7	6.85	6.23	NS-FP	6.78	6.77	NS-NW	6.64	6.74	6.67	NS-NW	
	Dec-03	NA	NA	NA	NA	NA	NA	NA	6.9	6.6	6.7	7.4	6.9	7.1	7	NS-FP	7.1	6.4	NS-FP	7	6.8	NS-NW	NA	NA	NA	NS-NW	
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	6.7	NA	7	7	6.8	6.8	6.7	6.7	NS-FP	6.7	NS-FP	6.7	6.8	6.4	NA	NA	NA	7	
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	8.7	NS-FP	8.6	8.9	6.9	6.7	6.7	6.7	NS-FP	6.9	NS-FP	6.8	6.7	NA	8.1	4.3	4.6	5.8	
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	6.67	NS-FP	6.65	7	6.79	6.74	6.8	6.7	NS-FP	6.79	NS-FP	6.26	6.74	NA	NA	NA	NA	NS	
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	8.9	NS-FP	8.6	8.9	6.6	6.8	6.6	6.8	NS-FP	6.4	NS-FP	6.5	NS-FP	NS-NW	NA	NA	NA	NS-NW	
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	6.55	7.4	NS-FP	6.47	8.34	8.87	8.82	7.51	7.15	6.83	NS-FP	7.04	NS-FP	7.24	NA	NA	NA	6.84	
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	6.59	6.39	6.39	6.6	8.3	8.42	7.48	6.49	6.52	7.66	NS-FP	6.49	6.8	6.62	NA	NA	NA	6.7	
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	7.2	7	6.96	7	6.94	7.05	7.1	7.01	6.9	7	NS-FP	NS-FP	7.1	6.87	7	NA	NA	NA	6.69
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	7.04	6.76	6.93	6.65	6.85	6.92	7.03	6.81	6.75	6.97	NS-FP	NS-FP	7.03	NS-FP	NS-NW	NA	NA	NA	6.52
TPH-gas	Feb-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Nov-04	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Oct-01	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Feb-02	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Jun-02	72,400	14,800	22,500	NS-FP	Table 2	8,530	NS-FP	5,300	Table 2	22,700	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Oct-02	52,300	7,370	29,900	NS-FP	NS-FP	5,300	52,300	1,730	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		
	Dec-02	NA	9,330	11,400	NS-FP	NS-FP	6,250	NS-FP	1,530	68,300	22,600	9,420	98	7,130	328	3,250	77	41,700	107,000	61	405						
	Mar-03	NA	15,800	12,200	NS-FP	NS-FP	3,470	NS-FP	2,500	85,100	24,700	1,730	<50	1,480	270	5,350	<50	83,900	177,000	52	745						
	Jun-03	NA	NA	NA	NA	NA	NA	NA	1,280	69,600	30,200	1,300	106	89	228	1,480	<50	44,900	NA	<50	998	NS-NW	<50	<50	<50	26,400	
	Sep-03	NA	NA	NA	NA	NA	NA	NA	1,280	77,200	51,500	5,390	64	521	790	Table 2	<50	46,600	Table 2	1080	2,140	NS-NW	NA	NA	NA	NS-NW	
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1,280	43,500	4,410	<50	154	1,680	NS-FP	<50	NS-FP	NS-FP	<50	2,650	3,080	NA	NA	NA	41,600		
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1,430	Table 2	43,500	1,780	<50	120	172	NS-FP	<50	NS-FP	NS-FP	<50	511	NA	NA	NA	NA		
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1,350	NS-FP	43,300	1,780	<50	120	172	NS-FP	<50	NS-FP	NS-FP	<50	6,090	NS-NW	NA	NA	NS		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1,500	NS-FP	82,400	1,730	224	484	1,040	NS-FP	<50	NS-FP	NS-FP	<50	8,090	NS-NW	NA	NA	NS		
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1,530	NS-FP	95,500	2,290	205	225	319	NS-FP	129	NS-FP	NS-FP	139	NS-FP	NS-NW	140	213	198	NS-NW	
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	41,100	2,120	NS-FP	47,600	1,890	239	173	3,080	59,400	145	NS-FP	NS-FP	148	NS-FP	3,440	103	134	181	75,600
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	48,600	1,580	326,000	41,000	1,880	259	433	3,890	73,000	128	NS-FP	NS-FP	794	NS-FP	3,360	90.3	177	117	84,300
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	52,000	3,390	144,000	891,000	1,540	155	1,250	293	46,700	87.9	NS-FP	NS-FP	111	NS-FP	2,700	153	150	113	40,300
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	64,800	3,800	87,100	238,000	1,470	92.1	180	885	21,800	104	NS-FP	NS-FP	81.5	NS-FP	NS-NW	288	341	185	158,000

NA= Not Analyzed.

<= Abandoned Well.

NS-FP= Not Sampled Free Product present.

Table 4: Detected VOCs from Groundwater Sample Results using GC-MS

Table 4 (cont): Detected VOCs from Groundwater Sample Items

Table 4 (cont): Detected Genomic Variants

Table 4 (cont.): Detected VOCs from Groundwater Samples using EPA Method 25A

Table 4 (cont'd): Demographic Variables

Table 4 (cont.): Detected VOCs from Groundwater Sample Results Using EPA Method 8260 (µg/L)

VOCs	Date	MW-1	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-16	MW-17	MW-18	MW-19	MW-20	MW-21	MW-22	MW-23	MW-24	MW-25	MW-26		
n-Propylbenzene	Jun-02	<250	26.5	<125	NS-FP	<25	NS-FP	<100																					
	Oct-02	<500	44.2	<50	NS-FP	NS-FP	<25	<250	NS-FP	<25																			
	Dec-02	NA	<250	<250	NS-FP	NS-FP	<25	NS-FP	<25	<2,500	259	89.5	<5	<125	<50	<250	<5	<500	1 <2,510	<5	<25								
	Mar-03	NA	<1,000	<500	NS-FP	NS-FP	<25	NS-FP	<25	<1,500	452	131	<5	<125	<50	<125	<5	<2,500	1 <2,510	<5	<25								
	Jun-03	NA	<200	<200	NS-FP	NS-FP	<50	NS-FP	<25	<200	<400	<10	<2	<2	<5	<50	<2	<400	1 <1,000	<5	<2	<20	<2	<2	<2	<100			
	Sep-03	NA	NA	NA	NS-NW	NS-FP	<25	NS-FP	<25	<400	303	45	<2	<2	<4	<50	<2	<200	1 NS-FP	<2	10.5	NS-NW	<2	<2	<2	<100			
	Dec-03	NA	NA	NA	NS-FP	NS-FP	<25	NS-FP	<25	<200	<400	123	<2	<2	<5	1 NS-FP	<2	1 220	1 NS-FP	22.9	<40	NS-NW	Table 5	Table 5	Table 5	Table 5	NS-NW		
	Mar-04	NA	NA	NA	NS-FP	NS-FP	<25	NS-FP	<25	Table 2	355	237	<2	<2	<2	1 NS-FP	<2	1 Table 2	1 Table 2	<2	14.3	<4	Table 5	Table 5	Table 5	<125			
	Jun-04	NA	NA	NA	NS-FP	NS-FP	<4	NS-FP	<4	210	122	<2	<2	<2	1 NS-FP	<2	1 NS-FP	<2	NS-FP	<2	<4	NS-NW	<2	<2	<2	<2	NA		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<13	NS-FP	231	184	<2	<2	<2	1 NS-FP	<2	1 NS-FP	<2	NS-FP	<2	13.4	NS-NW	<2	<2	<2	<2	NS-NW	
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<13	NS-FP	327	129	<2	<2	<2	1 NS-FP	<2	1 NS-FP	<2	NS-FP	<2	NS-FP	<2	NS-FP	<2	<2	<2	<2	NS-NW
	Mar-05	NA	NA	NA	NS-NW	NS-SW	NA	1.7	<5	NS-FP	220	122	<2	<2	<2	1 E1	<2	1 NS-FP	<2	NS-FP	<2	NS-FP	<2	NS-FP	<2	<2	<2	<2	<100
	Jun-05	NA	NA	NA	NS-NW	NS-SW	NA	132	<20	<400	<200	117	<2	<2	<40	1 <100	<2	1 NS-FP	1 NS-FP	<2	1 NS-FP	<20	<2	<2	<2	<2	<100		
	Sep-05	NA	NA	NA	NS-NW	NS-SW	NA	177	<20	<500	270	133	<2	6.6	<2	1 48.2	<2	1 NS-FP	1 NS-FP	<2	1 NS-FP	<40	<2	<2	<2	<2	<100		
	Dec-05	NA	NA	NA	NS-NW	NS-SW	NA	232	<20	1,690	248	105	<2	<2	<2	1 30.6	<2	1 NS-FP	1 NS-FP	<2	1 NS-FP	NS-NW	<2	<2	<2	<2	170		
Tetrafluoroethene	Feb-01	862	2,150	5,370	3,323	2,150	132																						
(FCE)	Nov-00	<2,500	<500	136	NS-FP	NS-FP	<500																						
	Oct-01	<100	<20	120	NS-NW	Table 2	100																						
	Feb-02	23	3.3	362	NS-FP	NS-FP	8.2																						
	Jun-02	26.8	<500	133	NS-FP	NS-FP	<25	NS-FP	122																				
	Oct-02	<200	<20	39.3	NS-FP	NS-FP	<100	NS-FP	193																				
	Dec-02	NA	<100	<100	NS-FP	NS-FP	<50	NS-FP	204	<1,000	<50	<10	87.1	<50	<20	1 268	8.1	534	1,240	8.7	53.1								
	Mar-03	NA	411	NS-FP	NS-FP	<50	NS-FP	135	<400	<200	<23	11	<50	<20	1 350	25	<1,000	1,460	3.3	17.8									
	Jun-03	NA	258	318	NS-FP	NS-FP	<50	NS-FP	132	<400	<400	<10	181	21.8	29.5	1 4B5	35.9	<400	1,460	48.9	<2	<20	4	4.1	12.3	1,922			
	Sep-03	NA	NA	NS-NW	NS-FP	NA	NS-FP	131	<400	<50	<12.5	145	26.3	36	273	15.1	<200	1 NS-FP	18.3	232	NS-NW	4.1	10.7	51	2,950				
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<5	<400	<400	<3.8	363	42.4	12.1	NS-FP	1B	<200	1 NS-FP	3.4	133	NS-NW	Table 5	Table 5	Table 5	Table 5	NS-NW		
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	149	Table 2	<100	3.8	514	42	63.2	1 NS-FP	36.2	Table 2	9.3	347	4	Table 5	Table 5	Table 5	Table 5	1,460			
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	123	NS-FP	<100	2.9	177	41.8	53.1	1 NS-FP	37.5	NS-FP	25	228	1 NS-NW	34.5	120	31.7	1,850				
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<50	3	239	40.5	56.5	1 NS-FP	20.4	NS-FP	35.6	491	1 NS-NW	1.7	<2	3.6	NA						
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	57.9	NS-FP	<200	<2	53.8	10.2	38.2	1 NS-FP	81.1	1 NS-FP	27.1	NS-FP	NS-NW	52.1 SM	73.1 SM	66.1 SM	NS-NW				
	Mar-05	NA	NA	NA	NS-NW	NS-SW	NA	<200	98.5	NS-FP	<200	5.4	56.9	23.7	87.6	38.8	117	1 NS-FP	1 NS-FP	106	NS-FP	<40	65.1 SM	74.7 SM	46.6 SM	2,840			
	Jun-05	NA	NA	NA	NS-NW	NS-SW	NA	<43	143	<400	<200	6.8	437	47.5	45.6	173	72.4	1 NS-FP	39.8	NS-FP	<40	49.1 SM	47.2 SM	51.6 SM	2,950				
	Sep-05	NA	NA	NA	NS-NW	NS-SW	NA	<200	137	<500	<200	5.9	40.1	54.8	99.6	369	76.8	1 NS-FP	35.3	NS-FP	<40	124 SM	52.1 SM	63.7 SM	1,070				
	Dec-05	NA	NA	NA	NS-NW	NS-SW	NA	<20	152	<500	<200	4.2	26.4	25.7	28.6	293	36.3	1 NS-FP	21.3	NS-FP	NS-NW	19.3 SM	66 SM	41 SM	3,150				
1,1,1-Trifluoroethane	Feb-94	9,370	3,470	444	36,200	114,000	90																						
(1,1,1-TCA)	Nov-00	<2,500	<500	70	NS-FP	NS-FP	<500																						
	Oct-01	<250	<50	<125	NS-NW	Table 2	<25																						
	Feb-02	<125	<12.5	<100	NS-FP	NS-FP	<10																						
	Jun-02	<250	<500	<125	NS-FP	NS-FP	<25	NS-FP	<100																				
	Oct-02	<500	<50	<50	NS-FP	NS-FP	<250	NS-FP	92																				
	Dec-02	NA	<250	<250	NS-FP	NS-FP	<125	NS-FP	32.3	<13,600	52.8	<21	<2	230	<50	<250	6	1,150	31,501	<5	<25								
	Mar-03	NA	<1,000	<500	NS-FP	NS-FP	<125	NS-FP	35	12,300	<500	14	1.4	27.5	<50	33.5	9.5	865	37,803	<5	14								
	Jun-03	NA	150	<400	NS-FP	NS-FP	<50	NS-FP	13.5	8,430	<400	19	<2	3.4	10.7	42.5	2	260	81,201	25	7C	<23	<2	<2	<2	<2	1,250		
	Sep-03	NA	NA	NA	NS-NW	NS-FP	NA	NS-FP	<20	4,510	<50	6.7	<2	8.9	6.4	<50	8	420	NS-FP	8.6	130	NS-NW	<2	<2	<2	<2	1,750		
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<2	7,460	652	10.7	<2	<4	<5	NS-FP	2.2	1,130	NS-FP	81.7	132	NS-NW	Table 5	Table 5	Table 5	Table 5	NS-NW		
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	11.1	Table 2	170	8.3	<2	<2	7.7	NS-FP	<2	Table 2	1 20.9	136	<4	Table 5	Table 5	Table 5	Table 5	7,350			
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	24	NS-FP	25	<2	<2	<2	4.5	NS-FP	7.4	NS-FP	3.4	<2	<2	<2	<2	<2	<2	<2	5,730		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	27.5	NS-FP	485	24	<2	<2	5.2	NS-FP	<2	NS-FP	3.2	312	NS-NW	<2	<2	<2	<2	NA			
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	27.5	NS-FP	290	<2	<2	<4	2.2	NS-FP	<2	NS-FP	<2	NS-FP	<2	NS-FP	<2	<2	<2	NS-NW			
	Mar-05	NA	NA	NA	NS-NW	NS-SW	NA	NA	321	13.5	NS-FP	158	<5	<2	<2	50	<2	NS-FP	<2	NS-FP	<4	<2	<2	<2	<2	3,900			
	Jun-05	NA	NA	NA	NS-NW	NS-SW	NA	NA	302	<20	1,410	117	<2	<2	<2	<40	<100	<2	NS-FP	<2	NS-FP	<2	NS-FP	<2	<2	<2	6,200		
	Sep-05	NA	NA	NA	NS-NW	NS-SW</																							

VOCs		Date	MW-1	MW-2	MW-3	MW-4	MW-5	MW-7	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-16	MW-17	MW-18	MW-19	MW-20	MW-21	MW-22	MW-23	MW-24	MW-25	MW-26		
Trichlorethene (TCE)	Feb-94	7,180	3,040	1,730	14,30	1,230	45																						
	Nov-00	<250	<50	1,500	NS-NW	NS-FP	<50																						
	Oct-01	<100	<20	100	NS-NW	Table 2	<10																						
	Feb-02	23	2.5	260	NS-FP	NS-FP	8.8																						
	Jun-02	<250	<50	134	NS-FP	NS-FP	<25	NS-FP	<100	NS-FP																			
	Oct-02	<250	<20	28	NS-FP	NS-FP	<100	NS-FP	566																				
	Dec-02	NA	<100	<100	NS-FP	NS-FP	<50	NS-FP	504	<1,000	<50	<10	77.2	<50	<20	274	3	945	1,740	2.9	55.7								
	Mar-03	NA	<400	1,830	NS-FP	NS-FP	<50	NS-FP	39	<400	<200	<20	26.6	<50	134	430	74	613	2,360	1.5	31.7								
	Jun-03	NA	'82	806	NS-FP	NS-FP	<50	NS-FP	419	<400	<400	<10	72.7	4	13.6	438	6.5	173	3,820	10	95	<20	2.3	2.3	20.4	1,330			
	Sep-03	NA	NA	NA	NS-NW	NS-FP	NA	NS-FP	47	<400	<50	7.5	56.2	12.1	15	2,530	3.9	<250	NS-FP	8.2	180	NS-NW	<2	11.5	25	2,130			
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	1.7	<400	<400	<5	47	22.6	8.3	NS-FP	7.3	163	NS-FP	4.4	140	Table 5	NS-NW						
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	37.2	Table 2	<100	<5	18.5	16.1	17.6	NS-FP	9.5	Table 2	Table 2	2.5	240	<2	Table 5	Table 5	Table 5	Table 5	3,000		
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	296	NS-FP	<100	<4	52.7	<2	21.5	NS-FP	9.1	NS-FP	NS-FP	6.7	108	NS-NW	22.9	65.7	42.9	<40			
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	283	NS-FP	<50	<4	39.2	19.8	12.1	NS-FP	17.3	NS-FP	NS-FP	12.2	321	NS-NW	<2	<2	37	NA			
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	214	NS-FP	<200	<2	24.3	24.2	47	NS-FP	29.3	NS-FP	NS-FP	12.6	NS-FP	NS-FP	27.7	33.9	59	65.2	NS-NW		
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	<200	31.9	NS-FP	<200	<5	134	9.6	49.7	164	23.8	NS-FP	NS-FP	25	NS-FP	<40	35.5	51.9	101	3,560			
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	<43	19	<400	<200	<2	54.5	14.4	<40	107	212	NS-FP	NS-FP	8.6	NS-FP	<40	31.2	74.0	98	46.3	5,060		
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	<200	114	<500	<200	2.2	120	23.5	23.5	271	25.8	NS-FP	NS-FP	21.2	NS-FP	<40	50.1	100	134	63.3	2,540		
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	<20	88.1	<500	<200	1.3	28.5	15.3	5.5	180	18.9	NS-FP	NS-FP	12.9	NS-FP	NS-NW	19.3	36	41	2,150			
1,2,4-Trimethylbenzene	Oct-01	1,590	18.9	345	NS-NW	Table 2	200																						
	Feb-02	2,800	231	568	NS-FP	NS-FP	234																						
	Jun-02	3,850	<500	878	NS-FP	NS-FP	236	NS-FP	<100																				
	Oct-02	2,120	<16	259	NS-FP	NS-FP	327	NS-FP	<25																				
	Dec-02	NA	232	356	NS-FP	NS-FP	<125	NS-FP	<25	<2,500	2,120	1,640	<5	27.0	<50	<230	<5	1,680	2,500	<5	<25								
	Mar-03	NA	360	441	NS-FP	NS-FP	225	NS-FP	<25	<1,500	2,950	703	<5	30	<50	238	238	1,490	8,080	19.5	18.5	<20	<2	<2	<2	<100			
	Jun-03	NA	<200	378	1 NS-FP	NS-FP	152	NS-FP	<20	1,740	1,400	20	<2	<2	<5	<50	<2	1,070	1,810	NS-FP	33.1	<40	NS-NW	Table 5	Table 5	Table 5	Table 5	NS-NW	
	Sep-03	NA	NA	NA	1 NS-NW	NS-FP	NA	NS-FP	<20	1,450	1,830	110	<2	<2	<4	<50	<2	1,680	NS-FP	<2	20.5	NS-NW	<2	<2	<2	555			
	Dec-03	NA	NA	NA	1 NS-FP	NS-FP	NA	NS-FP	<20	1,640	1,582	498	<2	<4	<5	NS-FP	<2	1,810	NS-FP	33.1	<40	NS-NW	Table 5	Table 5	Table 5	Table 5	1,140		
	Mar-04	NA	NA	NA	1 NS-FP	NS-FP	NA	NS-FP	<20	Table 2	2,060	1,200	<2	<2	<15	1 NS-FP	<2	Table 2	Table 2	<2	50	6.6	Table 5	Table 5	Table 5	Table 5	300		
	Jun-04	NA	NA	NA	1 NS-FP	NS-FP	NA	NS-FP	<4	1 NS-FP	1,410	555	<2	<2	<2	1 NS-FP	<2	NS-FP	NS-FP	<2	2	NS-NW	<2	<2	<2	832			
	Sep-04	NA	NA	NA	1 NS-FP	NS-FP	NA	NS-FP	<10	1 NS-FP	925	768	<2	<2	<3.1	1 NS-FP	<2	NS-FP	NS-FP	<2	151	NS-NW	<2	<2	<2	NA			
	Dec-04	NA	NA	NA	1 NS-FP	NS-FP	NA	NS-FP	<10	NS-FP	2,910	473	<2	<4	<2	1 NS-FP	<2	NS-FP	NS-FP	<2	NS-FP	NS-NW	<2	<2	<2	NS-NW			
	Mar-05	NA	NA	NA	1 NS-NW	NS-NW	NA	2,420	<6	NS-FP	1,540	211	<2	<2	<2	3,250	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<2	984			
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	2,760	<20	6,840	1,720	143	<2	<2	<40	2,210	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<2	1,130			
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	2,550	43.4	2,510	2,750	78.6	<2	74.5	<2	2,120	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<2	332			
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	4,200	<20	2,680	2,240	49.6	<2	<2	6.7	1,450	<2	NS-FP	NS-FP	<2	NS-FP	NS-NW	<2	<2	<2	564			
1,3,5-Trimethylbenzene	Oct-01	470	52.9	145	NS-NW	Table 2	25																						
	Feb-02	955	57.5	126	NS-FP	NS-FP	45.6																						
	Jun-02	1,170	57.5	<126	NS-FP	NS-FP	<25	NS-FP	<100																				
	Oct-02	574	67.6	57.8	NS-FP	NS-FP	<250	NS-FP	<25																				
	Dec-02	NA	<250	<250	NS-FP	NS-FP	<125	NS-FP	<25	<2,500	675	765	<5	106	<50	<250	<5	528	<2,500	<5	<25								
	Mar-03	NA	<1,000	<500	NS-FP	NS-FP	<30	NS-FP	<25	404	403	411	<5	125	<50	<125	<5	635	645	<5	<25								
	Jun-03	NA	<200	<400	NS-FP	NS-FP	<50	NS-FP	<20	398	440	19	<2	<5	<50	<2	506	1,532	<5	<2	<20	<2	<2	<2	<2	<2	<100		
	Sep-03	NA	NA	NA	NS-NW	NS-FP	<4	NA	NS-FP	<20	320	570	82	<2	<2	<4	<50	<2	400	NS-FP	<2	<10	NS-NW	<2	<2	<2	<2	170	
	Dec-03	NA	NA	NA	NS-FP	NS-FP	<20	NA	NS-FP	<20	412	506	294	<2	<4	<50	<2	459	NS-FP	13.8	<40	NS-NW	Table 5	Table 5	Table 5	Table 5	NS-NW		
	Mar-04	NA	NA	NA	NS-FP	NS-FP	<20	NA	NS-FP	<20	Table 2	619	<2	<2	<3.4	NS-FP	<2	Table 2	Table 2	<2	6.5	<4	Table 5	Table 5	Table 5	Table 5	300		
	Jun-04	NA	NA	NA	NS-FP	NS-FP	<4	NA	NS-FP	455	340	<2	<2	<2	NS-FP	<2	NS-FP	NS-FP	<2	<4	NS-NW	<2	<2	<2	<2	189			
	Sep-04	NA	NA	NA	NS-FP	NS-FP	<10	NS-FP	500	410	<2	<2	<2	NS-FP	<2	NS-FP	NS-FP	<2	<4	NS-NW	<2	<2	<2	<2	NA				
	Dec-04	NA	NA	NA	NS-FP	NS-FP	<10	NA	NS-FP	<10	NS-FP	1,440	260	<2	<4	<2	NS-FP	<2	NS-FP	NS-FP	<2	NS-FP	NS-NW	<2	<2	<2	NS-NW		
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	579	<5	NS-FP	488	175	<2	<2	<2	411	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<2	<2	216		
	Jun-05	NA	NA	NA	NS-NW	NS-NW	VA	700	<20	1,680	522	127	<2	<2	<43	322	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<2	<2	277		
	Sep-05	NA	NA	NA	NS-NW	NS-NW	VA	811	23.9	619	786	35.3	<2	<2	24.1	<2	252	<2	NS-FP	NS-FP	<2	NS-FP	<40	<2	<2	<			

Table 4 (cont.): Detected VOCs from Groundwater Sample Results using EPA Method 8260 (µg/L)

VOCs	Date	MW-1	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-16	MW-17	MW-18	MW-19	MW-20	MW-21	MW-22	MW-23	MW-24	MW-25	MW-26	MW-27				
Toluene	Feb-94	560	7,390	573	12,700	15,301	398																									
	Nov-00	4,000	57	3,700	NS-FP	NS-FP	805																									
	Oct-01	2,470	26	5,150	NS-NW	Table 1	975																									
	Feb-02	4,890	26.2	4,620	NS-FP	NS-FP	1,330																									
	Jun-02	5,180	102	4,780	NS-FP	NS-FP	1,280	NS-FP	<20																							
	Oct-02	5,390	39	4,610	NS-FP	NS-FP	2,560	NS-FP	<5																							
	Dec-02	NA	158	5,770	NS-FP	NS-FP	541	NS-FP	<5	19,600	1,230	29.6	1.2	2,840	14.4	<50	<1	1,730	13,500	3.3	6.7											
	Mar-03	NA	<200	2,310	NS-FP	NS-FP	938	NS-FP	<5	12,000	3,833	14.5	<1	230	<10	<25	<1	4,970	11,600	<1	<5											
	Jun-03	NA	<100	2,680	NS-FP	NS-FP	724	NS-FP	<10	10,950	4,623	<5	<1	<1	<2.6	<25	<1	5,513	13,300	7.2	<1	<13	<1	<1	<1	<1	<1	<EC				
	Sep-03	NA	NA	NA	NS-NW	NS-FP	NA	NS-FP	<10	13,800	4,033	<2.5	<1	<1	2	<25	<1	3,700	13,500	<1	13	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<1	13,500	6,570	9.7	<1	<2	3.2	NS-FP	<1	2,553	13,500	14.6	<1	NS-NW	Table 5	NS-NW								
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<10	Table 2	6,053	<2.5	<1	<1	54.6	NS-FP	<1	Table 2	Table 2	<1	17.5	16.4	Table 5									
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<2	NS-FP	9,003	3.6	<1	<1	43.3	NS-FP	<1	NS-FP	NS-FP	<1	94	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<5	NS-FP	16,200	1.5	<1	<1	131	NS-FP	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<5	NS-FP	16,300	<1	<1	<2	33.5	NS-FP	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	6,170	4.8	NS-FP	6,580	<2.5	<1	<1	42.2	62.5	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	15,900	
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	4,510	<10	12,800	7,830	<1	<1	196	148	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	14,200		
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	4,290	40.8	11,900	10,700	<1	<1	264	27.5	29.4	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	15,400	
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	4,630	<20	15,000	7,400	<1	<1	<2	54.5	<20	<1	NS-FP	NS-FP	1.1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	15,400	
Vinyl Chloride	Oct-01	1,350	75	<5	NS-NW	Table 2	186																									
	Feb-02	1,060	197	896	NS-FP	NS-FP	547																									
	Jun-02	<100	<200	<50	NS-FP	NS-FP	<10	NS-FP	<40																							
	Oct-02	2,860	2,710	12,290	NS-FP	NS-FP	884	NS-FP	123																							
	Dec-02	NA	2,720	12,730	NS-FP	NS-FP	423	NS-FP	107	4,100	198	1,100	6.2	<50	93.1	555	<2	<200	<1,000	<2	28.1											
	Mar-03	NA	1,840	7,870	NS-FP	NS-FP	200	NS-FP	92	3,690	1,180	66.6	2.6	<60	77.6	387	<2	<1,000	E30	<2	22.6											
	Jun-03	NA	4,500	2,380	NS-FP	NS-FP	360	NS-FP	173	3,410	1,830	36	3.6	<2	49	395	<2	<400	<1,000	<5	96.9	<2	<2	<2	<100							
	Sep-03	NA	NA	NA	NS-NW	NS-FP	NA	NS-FP	296	4,510	1,510	36	<2	5.2	51	588	<2	800	NS-FP	<2	3' 5	NS-NW	<2	<2	<2	<100						
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	52	3,700	1,520	13.1	<2	6.1	134	NS-FP	<2	<200	NS-FP	<2	47.3	NS-NW	Table 5	NS-NW								
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	155	Table 2	1,160	8.5	<1	<1	546	NS-FP	<1	Table 2	Table 2	<1	66	360	Table 5	450								
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	191	NS-FP	3,320	10.4	<1	2	13B	NS-FP	<1	NS-FP	NS-FP	<1	13.6	NS-NW	<1	<1	<1	<1	<1	<1	<1	<43		
	Sep-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	111	NS-FP	2,550	<10	<1	5.5	272	NS-FP	<1	NS-FP	NS-FP	<1	202	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Dec-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	32.9	NS-FP	5,410	3.6	<1	<2	34.7	NS-FP	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	<1		
	Mar-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	1,340	310	NS-FP	1,280	12.8	6.2	4.5	724	1,180	<1	NS-FP	NS-FP	<1	12	NS-FP	1,340	<1	<1	<1	<1	<1	<1	<1	138
	Jun-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	1,510	278	3,700	2,030	4.1	2.2	7.9	1,320	488	<1	NS-FP	NS-FP	<1	NS-FP	NS-FP	<1	<1	<1	<1	<1	<1	<1	<50	
	Sep-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	3,790	470	1,470	1,440	8.8	<1	19.8	174	1,08C	<1	NS-FP	NS-FP	<1	1,530	<1	<1	<1	<1	<1	<1	<1	<50		
	Dec-05	NA	NA	NA	NS-NW	NS-NW	NA	NA	4,050	340	608	2,160	4.4	<1	22	218	721	<1	NS-FP	NS-FP	<1	NS-FP	NS-NW	<1	<1	<1	<1	<1	<1	<1	<50	
Xyenes	Feb-94	2,182	7,790	1,014	4,362	4,710	186																									
	Nov-00	3,400	<500	2,500	NS-FP	NS-FP	247																									
	Oct-01	2,770	<2	3,720	NS-NW	Table 2	301																									
	Feb-02	3,760	14.8	3,070	NS-FP	NS-FP	1,280																									
	Jun-02	5,240	152	3,690	NS-FP	NS-FP	354	NS-FP	<20																							
	Oct-02	NA	73	2,570	NS-FP	NS-FP	576	NS-FP	<5																							
	Dec-02	NA	355	2,900	NS-FP	NS-FP	121	NS-FP	<5	4,690	748	242	<1	1,760	<10	<50	<1	2,690	3,840	<1	<5											
	Mar-03	NA	316	2,100	NS-FP	NS-FP	318	NS-FP	<10	2,330	1,820	28.1	<2	100	<20	<50	<2	4,200	4,960	<2	8.4											
	Jun-03	NA	170	1,760	NS-FP	NS-FP	238	NS-FP	<10	4,590	1,580	<5	<1	<1	<2.5	<25	<1	3,650	6,040	8.3	<1	<10	<1	<1	<1	<1	<1	1,050				
	Sep-03	NA	NA	NA	NS-NW	NS-FP	NA	NS-FP	<10	4,460	1,320	B	<1	<1	<2	<25	<1	2,620	NS-FP	<1	93	NS-NW	<1	<1	<1	<1	<1	6,673				
	Dec-03	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<1	4,580	2,520	157	<1	<2	<2.5	NS-FP	<1	2,610	NS-FP	<22	91.9	NS-NW	Table 5	NS-NW								
	Mar-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<10	Table 2	2,170	231	<1	<1	27.3	NS-FP	<1	Table 2	Table 2	<1	175	8.8	Table 5	9,320								
	Jun-04	NA	NA	NA	NS-FP	NS-FP	NA	NS-FP	<2	NS-FP	1,920	18.9	<1	<1	9.8	NS-FP	<1	NS-FP	NS-FP	<1	5.3	NS-NW	<1	<1	<1	<1	<1	<1	<1	9,320		
	Sep-04	NA	NA																													

Table 5: Detected VOCs from Diffusion Bag Groundwater Samples using EPA Method 8260 (µg/L)

	Date	Depth	MW-23	MW-24	MW-25
Screened Interval (feet bg)			71-81	67-77	71-81
DTW (ft)	15-Dec-03		42.65	45.69	47.35
	30-Mar-04		43.25	46.41	48.03
VOCs					
Acetone	15-Dec-03	1.5'	<25	<25	<25
	15-Dec-03	7.5'	<25	<25	<25
	30-Mar-04	2.5'	<25	<25	<25
	30-Mar-04	7.5'	<25	<25	<25
Benzene	15-Dec-03	1.5'	<1	<1	<1
	15-Dec-03	7.5'	<1	<1	<1
	30-Mar-04	2.5'	<1	<1	<1
	30-Mar-04	7.5'	<1	<1	<1
2-Butanone (MEK)	15-Dec-03	1.5'	<25	<25	<25
	15-Dec-03	7.5'	<25	<25	<25
	30-Mar-04	2.5'	<25	<25	<25
	30-Mar-04	7.5'	<25	<25	<25
Chloroethane	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
1,1-Dichloroethane	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
1,2-Dichloroethane	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
1,1-Dichloroethene	15-Dec-03	1.5'	6	14.6	7.4
	15-Dec-03	7.5'	6.1	<2	6.2
	30-Mar-04	2.5'	4.4	7.6	7.4
	30-Mar-04	7.5'	4.2	6.6	6.2
cis 1,2-Dichloroethene	15-Dec-03	1.5'	2.4	8.8	3.4
	15-Dec-03	7.5'	<2	5.7	<2
	30-Mar-04	2.5'	<2	11.7	<2
	30-Mar-04	7.5'	<2	11.3	<2

Table 5: Detected VOCs from Diffusion Bag Groundwater Samples using EPA Method 8260 (µg/L)

VOCs	Date	Depth	MW-23	MW-24	MW-25
trans 1,2-Dichloroethene	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
1,4 Dioxane	15-Dec-03	1.5'	<50	<50	<50
	15-Dec-03	7.5'	<50	<50	<50
	30-Mar-04	2.5'	<50	<50	<50
	30-Mar-04	7.5'	<50	<50	<50
Ethylbenzene	15-Dec-03	1.5'	<1	<1	<1
	15-Dec-03	7.5'	<1	<1	<1
	30-Mar-04	2.5'	<1	<1	<1
	30-Mar-04	7.5'	<1	<1	<1
Methylene Chloride	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
4-Methyl-2-pentanone	15-Dec-03	1.5'	<25	<25	<25
	15-Dec-03	7.5'	<25	<25	<25
	30-Mar-04	2.5'	<25	<25	<25
	30-Mar-04	7.5'	<25	<25	<25
Naphthalene	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
n-Propylbenzene	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
Tetrachloroethene	15-Dec-03	1.5'	30.6	75.4	37.1
	15-Dec-03	7.5'	14.8	24.3	37.2
	30-Mar-04	2.5'	38.2	225	30.3
	30-Mar-04	7.5'	37.7	263	24.9

Table 5: Detected VOCs from Diffusion Bag Groundwater Samples using EPA Method 8260 (µg/L)

VOCs	Date	Depth	MW-23	MW-24	MW-25
1,1,1-Trichloroethane	15-Dec-03	1.5'	3.2	2.3	<2
	15-Dec-03	7.5'	2.6	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
Trichloroethylene	15-Dec-03	1.5'	11.3	51.4	38.5
	15-Dec-03	7.5'	7.9	49.3	39.4
	30-Mar-04	2.5'	14.2	74.5	34.9
	30-Mar-04	7.5'	14.7	67.1	18.6
1,2,4-Trimethylbenzene	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
1,3,5-Trimethylbenzene	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
Toluene	15-Dec-03	1.5'	<1	<1	<1
	15-Dec-03	7.5'	<1	<1	<1
	30-Mar-04	2.5'	<1	<1	<1
	30-Mar-04	7.5'	<1	<1	<1
Vinyl Chloride	15-Dec-03	1.5'	<2	<2	<2
	15-Dec-03	7.5'	<2	<2	<2
	30-Mar-04	2.5'	<2	<2	<2
	30-Mar-04	7.5'	<2	<2	<2
Xylenes	15-Dec-03	1.5'	<1	<1	<1
	15-Dec-03	7.5'	<1	<1	<1
	30-Mar-04	2.5'	<1	<1	<1
	30-Mar-04	7.5'	<1	<1	<1
DTW= Depth to Water.					
Depth= Depth above well bottom.					
Blue= Chemicals stored on-site.					
Red= Transformation compounds.					

Table 6. Results for EPA Methods 376.1, 325.3, 310.1, 352.1, 375.4, 7380, 7460, 160.1, Colorimetry and Standard Method 4500 (mg/L)												
		First Water Wells					Upper A1 Zone Wells					
Compound	Date	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-17	MW-20	MW-21
Dissolved	Dec-03		12		100	3	1.6	2.9	2.4	0.9	2.2	3.4
Organic Carbon	Mar-04		8.6		240	3.1	1.3	2.4	5.6	0.6	1	3.3
	Jun-04		7.2		84	3.2	3.1	2.1	2.3	<1	1.5	1.4
	Sep-04		4.3		48	2.1	0.9	2.7	5.9	0.6	3.4	5.1
	Dec-04		4.5		26	2.9	1.5	1.7	2.4	0.9	1.6	NS-FP
	Mar-05		15		545	2.2	1.7	2.1	1	2	2.8	NS-FP
	Jun-05		20		125	3	4	3.4	12	NA	NA	NS-FP
	Dec-05	24	21	14	29	4.4	5	NA	NA	15	8.7	
Total Organic Carbon	Dec-03		13		105	3.7	1.9	3.1	2.6	1.2	2.6	3.7
	Mar-04		9.6		270	3.4	1.5	3.1	6.5	1	1.1	3.7
	Jun-04		7.9		94	3.5	3.4	2.4	2.5	1.2	1.7	1.7
	Sep-04		4.6		50	2.5	1	2.9	6.1	0.9	3.7	5.4
	Dec-04		5.1		34	3.1	1.6	2.4	2.8	1.6	2	NS-FP
	Mar-05		16		595	2.3	1.7	2.3	4.7	2.3	3.4	NS-FP
	Jun-05		21		49	3	4.6	3.8	13	NA	NA	NS-FP
TDS	Dec-05	23	22	17	30	4.1	3.7	NA	NA	17	9.8	NS-FP
	Jun-03		1,640		2,250	839	1,200	1,450	1,830	1,400	1,280	1,250
	Sep-03		1,600		1,935	735	1,185	1,205	1,195	1,675	1,235	1,296
	Dec-03		1,250		1,690	730	1,160	1,140	1,260	1,170	1,200	1,110
	Mar-04		2,620		1,660	1,570	1,210	855	873	1,310	2,020	1,080
	Jun-04		1,760		1,590	721	1,290	1,280	1,230	1,450	1,250	1,180
	Sep-04		1,700		1,370	578	1,190	1,170	1,240	1,080	1,300	1,180
Total Alkalinity	Dec-04		1,510		809	479	946	959	1,650	1,850	1,790	NS-FP
	Mar-05		1,650		2,170	551	988	1,140	1,030	1,210	934	NS-FP
	Jun-05		1,620		1,410	696	962	1,180	1,060	1,180	577	NS-FP
	Sep-05		796		825	659	1,060	1,230	1,200	1,200	1,210	NS-FP
	Dec-05	136	1,550	509.4	630	374	513	NA	NA	1,070	1,020	NS-FP
	Jun-03		525		960	290	430	433	455	460	425	472
	Sep-03		545		955	408	473	370	448	475	433	460
Carbonate/bicarbonate	Dec-03		540		912	340	435	350	465	430	479	530
	Mar-04		485		766	498	452	298	458	407	449	542
	Jun-04		430		696	505	435	373	456	433	438	440
	Sep-04		275		650	375	373	288	455	330	415	548
	Dec-04		370		695	455	443	401	445	430	443	NS-FP
	Mar-05		568		885	385	365	395	520	433	353	NS-FP
	Jun-05		610		635	355	401	375	530	420	272	NS-FP
Total Dissolved Solids	Sep-05		595		555	335	385	435	475	420	410	NS-FP
	Dec-05	583	595	545	573	318	375	NA	525	420	445	NS-FP
	Jun-03		612		1,152	348	516	519	546	552	510	567
	Sep-03		654		1,176	489	507	444	507	570	519	552
	Dec-03		324		547	204	261	210	279	258	287	318
	Mar-04		582		919	598	542	351	550	488	539	650
	Jun-04		262		424	308	265	228	278	264	267	268
Total Hardness	Sep-04		168		397	229	227	175	278	201	253	334
	Dec-04		171		177	61	116	244	271	262	273	NS-FP
	Mar-05		346		540	235	223	241	317	264	215	NS-FP
	Jun-05		372		387	217	244	229	323	256	166	NS-FP
	Sep-05		357		337	201	231	261	285	252	246	NS-FP
	Dec-05	355	363	332	351	194	229	NA	320	256	271	NS-FP
	Jun-03											

Table 6. (Continued) Results for EPA Methods 376.1, 325.3, 310.1, 352.1, 375.4, 7380, 7460, 160.1, Colorimetry and Standard Method 4500 (mg/L)												
First Water Wells Upper A1 Zone Wells												
Compound	Date	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13	MW-14	MW-15	MW-17	MW-20	MW-21
Chloride	Jun-03	241		425	70.9	101	92.2	95	96.4	87.9	87.9	
	Sep-03	241		383	57	99	142	106	170	92	142	
	Dec-03	238		344	74.4	106	160	113	106	99.3	135	
	Mar-04	221		441	76.2	92.6	92.6	104	95.3	123	158	
	Jun-04	198		332	78	119	122	102	106	109	116	
	Sep-04	132		334	54.5	123	197	129	102	91.9	129	
	Dec-04	152		158	54.5	103	98	113	98	112	NS-FP	
	Mar-05	253		384	54.5	92.6	123	169	264	215	NS-FP	
	Jun-05	284		287	35.5	115	135	156	121	70.9	NS-FP	
	Sep-05	269			99.3	45.4	96.4	128	121	122	106	NS-FP
	Dec-05	125	294	65.3	98	45.6	65.3	NA	144	125	114	NS-FP
Sulfide	Jun-03	<0.02		3.68	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
	Sep-03	<0.05		2.56	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
	Dec-03	<0.05		<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
	Mar-04	<0.02		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
	Jun-04	<0.02		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
	Sep-04	<0.02		<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
	Dec-04	<0.02		0.16	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	NS-FP
	Mar-05	<0.05		0.96	<0.05	<0.05	<0.05	0.48	<0.05	<0.05	NS-FP	
	Jun-05	<0.02		0.64	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	NS-FP	
	Sep-05	<0.03		1.12	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	NS-FP	
	Dec-05	0.48	<0.05	<0.05	0.16	<0.05	<0.05	NA	<0.05	<0.05	<0.05	NS-FP
Sulfate	Jun-03	264		7.9	108	214	182	279	206	176	182	
	Sep-03	250		26	85	230	202	285	215	215	230	
	Dec-03	783		16	47	533	399	287	387	501	287	
	Mar-04	595		<1	27.6	262	<1	<1	335	250	<1	
	Jun-04	707		3.49	42	143	603	735	164	81.4	518	
	Sep-04	490		<1	36.5	114	278	95	319	367	192	
	Dec-04	454		<1	28.1	162	112	140	120	195	NS-FP	
	Mar-05	141		<1	32.2	84.4	121	40.4	110	36.6	NS-FP	
	Jun-05	177		<1	68.9	133	170	101	137	83.8	NS-FP	
	Sep-05	119		<1	48.7	84.7	83.9	85.8	71.8	69.1	NS-FP	
	Dec-05	4.82	224	11.4	<1	76.6	98.8	NA	37	76.2	64.4	NS-FP
Nitrate	Jun-03	16.4		8.81	<0.01	27.8	25.1	29.7	27.8	24.2	23.8	
	Sep-03	0.138		<0.01	<0.01	0.027	0.012	0.029	<0.01	0.17	0.019	
	Dec-03	25.5		3.96	1.16	17.4	20.9	25.2	20.1	21.4	22.8	
	Mar-04	22.5		12.7	0.46	19.6	24.1	17.1	18	29.7	20	
	Jun-04	29		8.18	1.24	18	27	32	28.7	25.6	24	
	Sep-04	30.8		8.78	2.81	27.6	20.3	27	23.2	22.1	8.47	
	Dec-04	12.7		5.05	2.97	14.2	21.6	20.4	17.8	16.2	NS-FP	
	Mar-05	11.6		9.57	<0.01	11.9	17.7	19.2	11.9	20.6	NS-FP	
	Jun-05	7.8		4.9	3.1	16.1	18.6	11.8	15.7	18.5	NS-FP	
	Sep-05	5.2		8.96	2.8	21.6	22.2	18.3	14.9	21.8	NS-FP	
	Dec-05	10.8	16.3	4.11	8.2	6.7	12.2	NA	6.86	13.9	17.6	NS-FP

Table 6. (Continued) Results for EPA Methods 376.1, 325.3, 310.1, 352.1, 375.4, 7380, 7460,

160.1, Colorimetry and Standard Method 4500 (mg/L)											
Compound	Date	First Water Wells				Upper A1 Zone Wells					
		MW-9	MW-11	MW-12	MW-13	MW-14	MW-15	MW-17	MW-20	MW-21	
Total Iron	Jun-03	<0.1	10.7	0.16	0.14	<0.1	0.2	0.43	0.22	<0.1	
	Sep-03	<0.05	18.7	0.41	<0.05	<0.05	<0.05	0.26	<0.05	<0.05	
	Dec-03	0.36	30.6	3.65	0.19	0.14	0.38	0.36	0.24	1.2	
	Mar-04	0.15	10.5	4.14	<0.1	<0.1	<0.1	<0.1	0.62	<0.1	
	Jun-04	<0.1	5.6	<0.1	0.12	0.2	0.2	0.15	<0.1	0.2	
	Sep-04	0.12	5.1	<0.1	<0.1	<0.1	0.13	<0.1	<0.1	<0.1	
	Dec-04	<0.1	1.65	0.36	0.45	0.4	0.25	0.17	0.13	NS-FP	
	Mar-05	<0.1	1.87	0.25	<0.1	<0.1	0.11	<0.1	<0.1	NS-FP	
	Jun-05	<0.1	0.68	0.17	0.16	<0.1	0.1	<0.1	<0.1	NS-FP	
	Sep-05	<0.1	7.5	1.4	<0.1	<0.1	0.3	<0.1	<0.1	NS-FP	
	Dec-05	0.11	<0.1	0.59	0.61	<0.1	NA	<0.1	<0.1	NS-FP	
Ferrous Iron	Jun-03	<0.05	0.49	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	
	Sep-03	<0.05	9.98	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	
	Dec-03	0.15	2.32	0.73	0.16	0.21	0.21	0.22	0.14	0.17	
	Mar-04	<0.05	2.62	2.25	<0.05	0.31	0.57	<0.05	0.1	0.86	
	Jun-04	<0.05	2.42	0.15	<0.05	0.24	0.17	<0.05	<0.05	0.48	
	Sep-04	<0.05	1.46	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	
	Dec-04	<0.05	<0.05	0.11	0.19	0.08	0.23	0.07	<0.05	NS-FP	
	Mar-05	<0.05	<0.05	0.25	<0.05	<0.05	0.13	<0.05	<0.05	NS-FP	
	Jun-05	<0.05	0.42	<0.05	0.18	<0.05	<0.05	<0.05	<0.05	NS-FP	
	Sep-05	<0.05	0.42	0.14	0.1	0.1	0.07	0.07	0.09	NS-FP	
	Dec-05	<0.05	<0.05	0.1	<0.05	<0.05	NA	<0.05	<0.05	NS-FP	
Manganese	Jun-03	<0.1	6.7	1.6	<0.1	<0.1	0.4	<0.1	<0.1	0.43	
	Sep-03	0.07	12.5	2.49	0.66	0.42	0.4	<0.05	0.12	0.64	
	Dec-03	0.15	13.5	1.47	0.22	1.02	1.14	0.23	0.12	1.96	
	Mar-04	0.11	4.71	1.12	0.13	0.15	1.11	0.09	0.14	1.78	
	Jun-04	0.2	6.6	0.9	<0.05	0.2	0.4	<0.05	<0.05	0.1	
	Sep-04	0.54	9.04	1.12	0.12	0.37	1.49	0.08	0.09	1.79	
	Dec-04	0.12	5.19	1.25	<0.05	0.09	0.76	<0.05	<0.05	NS-FP	
	Mar-05	0.49	15	2.52	<0.05	<0.05	3.19	<0.05	0.33	NS-FP	
	Jun-05	0.35	8.85	2.55	0.1	<0.05	3.32	<0.05	0.16	NS-FP	
	Sep-05	0.4	7.94	3.36	0.16	0.37	0.74	0.06	0.3	NS-FP	
	Dec-05	2.07	0.23	2.49	6.05	2.62	0.25	NA	0.2	<0.05	
Ethylene	Mar-04	22.7	1,001	176	<5	255	<5	<5	<5	1,080	
	Jun-04	28.5	2,120	174	<5	<5	15.5	<5	<5	<5	
	Sep-04	30	4,620	46	<5	<5	<5	<5	<5	49	
	Dec-04	10.5	2,580	27	<5	<5	25.5	<5	<5	NS-FP	
	Mar-05	32	2,011	5	<5	<5	31.5	<5	<5	NS-FP	
	Jun-05	<5	7430	33	<5	<5	313	<5	<5	NS-FP	
	Sep-05	<5	916	<5	<5	<5	34	<5	<5	NS-FP	
	Dec-05	804	46	193	1,803	<5	<5	NA	<5	<5	

WELL GAUGING DATA

Project # 051216-SM1 Date 12/16/05 Client Clean Soils

Site 8915 Scarsen Ave., Santa Fe Springs

Well ID	Well Size (in.)	Sheen / Odor	Depth to Immiscible Liquid (ft.)	Thickness of Immiscible Liquid (ft.)	Volume of Immiscibles Removed (ml)	Depth to water (ft.)	Depth to well bottom (ft.)	Survey Point: TOB or TOC	
MW-4	4					26.59	26.63	TOC	
MW-6	4					29.90	30.24		
MW-8	4					33.26	40.69		
MW-9	4					33.56	45.99		
MW-10	4					33.00	40.59		
MW-11	2					32.71	39.81		Trans.
MW-12	2					35.28	43.96		Trans.
MW-13	2					40.33	62.47		Trans.
MW-14	2					40.72	62.49		
MW-15	2					42.14	62.20		
MW-16	2					32.23	45.22		
MW-17	2					38.83	66.20		
MW-20	2					39.68	67.33		
MW-21	2					41.20	63.10		Trans.
MW-22	2					39.88	40.10		
MW-23	4					37.65	80.14		
MW-24	4					40.98	76.90		↓

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

Table 7: Dissolved Metal Sample Results (mg/L)

Dissolved Metals	EPA Method	Date	MW-1	MW-2	MW-3	MW-4	MW-6	MW-7	MW-8	MW-9	MCLs
Antimony	7040	Oct-01	<0.5	<0.5	<0.5	NS-FP	NS-FP	<0.5			0.006
		Feb-02	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1			
		Jun-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
		Oct-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
Arsenic	7060	Oct-01	0.026	0.061	<0.005	NS-FP	NS-FP	0.071			0.05
		Feb-02	0.068	0.044	0.006	NS-FP	NS-FP	0.149			
		Jun-02	0.064	0.046	<0.005	NS-FP	NS-FP	0.145	NS-FP	<0.005	
		Oct-02	0.015	0.038	<0.005	NS-FP	NS-FP	0.078	NS-FP	<0.005	
Barium	7080	Oct-01	<0.5	<0.5	<0.5	NS-FP	NS-FP	<0.5			1
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	0.8	0.88	0.51	NS-FP	NS-FP	0.68	NS-FP	0.66	
		Oct-02	0.984	0.962	0.91	NS-FP	NS-FP	0.897	NS-FP	0.683	
Beryllium	7090	Oct-01	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05			0.004
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	<0.002	<0.002	<0.002	NS-FP	NS-FP	<0.002	NS-FP	<0.002	
		Oct-02	<0.002	<0.002	<0.002	NS-FP	NS-FP	<0.002	NS-FP	<0.002	
Cadmium	7130	Oct-01	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05			0.005
		Feb-02	<0.04	<0.04	<0.04	NS-FP	NS-FP	<0.04			
		Jun-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
		Oct-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
Chromium	7190	Oct-01	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1			0.05
		Feb-02	<0.02	<0.02	<0.02	NS-FP	NS-FP	<0.02			
		Jun-02	0.015	0.016	0.016	NS-FP	NS-FP	0.017	NS-FP	0.019	
		Oct-02	0.0188	0.0185	0.02	NS-FP	NS-FP	0.021	NS-FP	0.024	
Cobalt	7200	Oct-01	<0.1	0.12	<0.1	NS-FP	NS-FP	<0.1			None
		Feb-02	<0.04	<0.04	<0.04	NS-FP	NS-FP	<0.04			
		Jun-02	0.23	0.2	0.18	NS-FP	NS-FP	0.11	NS-FP	0.18	
		Oct-02	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1	NS-FP	<0.1	

Table 7 (cont.): Dissolved Metal Sample Results (mg/L)

<u>Dissolved Metals</u>	<u>EPA Method</u>	<u>Date</u>	<u>MW-1</u>	<u>MW-2</u>	<u>MW-3</u>	<u>MW-4</u>	<u>MW-6</u>	<u>MW-7</u>	<u>MW-8</u>	<u>MW-9</u>	<u>MCLs</u>
Copper	7210	Oct-01	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05			1.3
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1	NS-FP	<0.1	
		Oct-02	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1	NS-FP	<0.1	
Lead	7240	Oct-01	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1			0.05
		Feb-02	<0.002	<0.002	<0.002	NS-FP	NS-FP	<0.002			
		Jun-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
		Oct-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
Mercury	7471	Oct-01	<0.001	<0.001	<0.001	NS-FP	NS-FP	<0.001			0.002
		Feb-02	<0.001	<0.001	<0.001	NS-FP	NS-FP	<0.001			
		Jun-02	<0.001	<0.001	<0.001	NS-FP	NS-FP	<0.001	NS-FP	<0.001	
		Oct-02	<0.001	<0.001	<0.001	NS-FP	NS-FP	<0.001	NS-FP	<0.001	
Molybdenum	7480	Oct-01	<0.4	<0.4	<0.4	NS-FP	NS-FP	<0.4			0.035*
		Feb-02	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1			
		Jun-02	<0.035	<0.035	<0.035	NS-FP	NS-FP	<0.035	NS-FP	<0.035	
		Oct-02	<0.035	<0.035	<0.035	NS-FP	NS-FP	<0.035	NS-FP	<0.035	
Nickel	7520	Oct-01	<0.1	<0.1	<0.1	NS-FP	NS-FP	<0.1			0.1
		Feb-02	<0.04	<0.04	<0.04	NS-FP	NS-FP	<0.04			
		Jun-02	0.13	0.13	0.13	NS-FP	NS-FP	0.13	NS-FP	0.13	
		Oct-02	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05	NS-FP	<0.05	
Selenium	7740	Oct-01	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			0.05
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
		Oct-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005	NS-FP	<0.005	
Silver	7760	Oct-01	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05			0.1
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	<0.01	<0.01	<0.01	NS-FP	NS-FP	<0.01	NS-FP	<0.01	
		Oct-02	<0.01	<0.01	<0.01	NS-FP	NS-FP	<0.01	NS-FP	<0.01	

Table 7 (cont.): Dissolved Metal Sample Results (mg/L)

<u>Dissolved Metals</u>	<u>EPA Method</u>	<u>Date</u>	<u>MW-1</u>	<u>MW-2</u>	<u>MW-3</u>	<u>MW-4</u>	<u>MW-6</u>	<u>MW-7</u>	<u>MW-8</u>	<u>MW-9</u>	<u>MCLs</u>
Thallium	7840	Oct-01	<0.2	<0.2	<0.2	NS-FP	NS-FP	<0.2			0.002
		Feb-02	<0.005	<0.005	<0.005	NS-FP	NS-FP	<0.005			
		Jun-02	<0.002	<0.002	<0.002	NS-FP	NS-FP	<0.002	NS-FP	<0.002	
		Oct-02	<0.002	<0.002	<0.002	NS-FP	NS-FP	<0.002	NS-FP	<0.002	
Vanadium	7910	Oct-01	<0.5	<0.5	<0.5	NS-FP	NS-FP	<0.5			0.06*
		Feb-02	0.03	0.05	0.16	NS-FP	NS-FP	0.14			
		Jun-02	<0.06	<0.06	<0.06	NS-FP	NS-FP	<0.06	NS-FP	<0.06	
		Oct-02	<0.06	<0.06	<0.06	NS-FP	NS-FP	<0.06	NS-FP	<0.06	
Zinc	7950	Oct-01	<0.05	<0.05	<0.05	NS-FP	NS-FP	<0.05			5
		Feb-02	<0.01	<0.01	<0.01	NS-FP	NS-FP	<0.01			
		Jun-02	0.07	0.04	0.05	NS-FP	NS-FP	0.04	NS-FP	0.23	
		Oct-02	<0.01	<0.01	<0.01	NS-FP	NS-FP	<0.01	NS-FP	<0.01	

NS-FP= Not Sampled Free Product present.

MCLs= Maximum Contaminant Levels.

*= Health Advisories.

Former Angeles Chemical Co. Free Product Removal Data Summary

Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-1	11/30/2000	Sheen	None	0	0	0
	10/30/2001	Sheen	None	0	0	0
	2/15/2002	0.02	None	0	0	0
	11/13/2002	0.03	None	0	0	0
					Mw-1 Total Liters Removed:	0.000
Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-4	10/30/2001	Sheen	None	0	0	0
	2/15/2002	0.06	None	0	0	0
	10/7/2002	Not measured	None	0	0	0
	6/30/2004	0.2	None	0	0	0
	7/23/2004	0.17	None	0	0	0
	9/16/2004	0.16	Bailer	15 mL	15	15
	9/28/2004	0.14	None	0	0	15
	10/11/2004	0.14	Bailer	15 mL	15	30
	10/22/2004	0.12	None	0	0	30
	11/11/2004	0.12	None	0	0	30
	11/24/2004	0.12	None	0	0	30
	12/21/2004	0.13	Bailer	10 mL	10	40
	1/4/2005	0.12	None	0	0	40
		None		0	0	40
					MW-4 Total Liters Removed:	0.040
Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-6	11/30/2000	Not measured	None	0	0	0
	10/30/2001	0.5	None	0	0	0
	1/18/2002	0.69	Bailer	1.0 gallon	3785	3785
	2/15/2002	0.94	Bailer	0.5 gallon	1892	5677
	6/7/2002	1	Bailer	1.0 gallon	3785	9462
	6/10/2002	0.6	Bailer	0.5 gallon	1892	11354
	6/13/2002	0.34	Bailer	0.5 gallon	1893	13247
	6/14/2002	Not measured	Bailer	0.5 gallon	1893	15140
	10/7/2002	Not measured	None	0	0	15140
	12/2/2002	0.37	None	0	0	15140
	9/16/2004	0.02	None	0	0	15140
	9/28/2004	0.02	None	0	0	15140
	10/11/2004	0.01	None	0	0	15140
	10/22/2004	0.01	None	0	0	15140
	11/11/2004	0.09	None	0	0	15140
	11/24/2004	0.05	None	0	0	15140
	12/21/2004	0.04	Bailer	25 mL	25	15165
	1/4/2005	0.02	None	0	0	15165
		None		0	0	15165
					MW-6 Total Liters Removed:	15.165

Former Angeles Chemical Co. Free Product Removal Data Summary						
Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-8	6/7/2002	0.84	Bailer	2 gallons	7570	7570
	6/10/2002	0.11	None	0	0	7570
	6/13/2002	0.87	Bailer	1 gallon	3785	11355
	6/14/2002	Not Measured	Bailer	3 gallons	11355	22710
	10/7/2002	Not Measured	None	0	0	22710
	12/2/2002	0.44	None	0	0	22710
	12/18/2002	Not Measured	Bailer	1 gallon	3785	26495
	12/18/2002	0.26	Bailer	1 L	1000	23710
	2/8/2004	0.24	Bailer	100 mL	100	23810
	2/10/2004	0.36	Bailer	100 mL	100	23910
	2/11/2004	0.1	None	0	0	23910
	2/13/2004	Not Measured	None	0	0	23910
	2/14/2004	0.15	Bailer	50 mL	50	23960
	2/16/2004	Not Measured	None	0	0	23960
	2/17/2004	0.08	None	0	0	23960
	2/18/2004	0.08	None	0	0	23960
	3/19/2004	0.19	Bailer	150 mL	150	24110
	4/30/2004	0.75	Bailer	250 mL	250	24360
	5/27/2004	0.3	Bailer	50 mL	50	24410
	6/30/2004	0.37	Bailer	50 mL	50	24460
	7/9/2004	0.1	Bailer	10 mL	10	24470
	7/23/2004	0.34	Bailer	20 mL	20	24490
	8/13/2004	0.34	Bailer	50 mL	50	24540
	9/16/2004	0.46	Bailer	250 mL	250	24790
	9/28/2004	0.41	Bailer	300 mL	300	25090
	10/11/2004	0.36	Bailer	350 mL	350	25440
	10/22/2004	0.4	Bailer	400 mL	400	25840
	11/11/2004	0.15	Bailer	75 mL	75	25915
	11/24/2004	0.18	Bailer	50 mL	50	25965
	12/8/2004	0.32	Bailer	250 mL	250	26215
	12/21/2004	0.24	Bailer	150 mL	150	26365
	1/4/2005	0.21	Bailer	125 mL	125	26490
	4/2/2005	0		0	0	
MW-8 Total Liters Removed:						26.490

Former Angeles Chemical Co. Free Product Removal Data Summary						
Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-10	3/19/2004	0.29	Bailer	0.25 gallons	946	946
	4/30/2004	0.4	Bailer	100 mL	100	1046
	5/27/2004	0.82	Bailer	0.5 gallons	1893	2939
	6/30/2004	0.51	Bailer	0.25 gallons	946	3885
	7/9/2004	0.12	Bailer	15 mL	15	3900
	7/23/2004	0.26	Bailer	10 mL	10	3910
	8/13/2004	1.18	Bailer	1 gallon	3785	7695
	9/16/2004	1.43	Bailer	1.25 gallons	4731	12426
	9/28/2004	0.57	Bailer	500 mL	500	12926
	10/11/2004	0.54	Bailer	600 mL	600	13526
	10/22/2004	0.63	Bailer	500 mL	500	14026
	11/11/2004	0.29	Bailer	200 mL	200	14226
	11/24/2004	0.2	Bailer	75 mL	75	14301
	12/8/2004	0.15	Bailer	50 mL	50	14351
	12/21/2004	0.18	Bailer	100 mL	100	14451
	1/4/2005	0.11	Bailer	500 mL	50	14501
	1/20/2005	0.11	Bailer	100 mL	100	14601
	2/1/2005	0.12	Bailer	100 mL	100	14701
	2/16/2005	0.06	Bailer	50 mL	50	14751
	3/11/2005	0.01		0	0	14751
	4/2/2005	0		0	0	
				MW-10 Total Liters Removed:		14,751
<hr/>						
MW-16	1/29/2004	0.51	None	0	0	0
	2/8/2004	0.51	Bailer	250 mL	250	250
	2/10/2004	0.37	Bailer	150 mL	150	400
	2/11/2004	0.29	Bailer	100 mL	100	500
	2/13/2004	Not Measured	None	0	0	500
	2/14/2004	Not Measured	None	0	0	500
	2/16/2004	Not Measured	None	0	0	500
	2/17/2004	Not Measured	None	0	0	500
	2/18/2004	Not Measured	None	0	0	500
	3/19/2004	0.19	Bailer	150 mL	150	650
	4/30/2004	0.41	Bailer	100 mL	100	750
	5/27/2004	0.08	Bailer	25 mL	25	775
	6/30/2004	0.34	Bailer	25 mL	25	800
	7/9/2004	0.24	Bailer	10 mL	10	810
	7/23/2004	0.24	Bailer	10 mL	10	820
	8/13/2004	0.28	Bailer	50 mL	50	870
	9/16/2004	0.12	Bailer	20 mL	20	890
	9/28/2004	0.13	Bailer	20 mL	20	910
	10/11/2004	0.06	None	0	0	910
	10/22/2004	0.11	Bailer	15 mL	15	925
	11/11/2004	0.04	None	0	0	925
	11/24/2004	0.02	None	0	0	925
	12/21/2004	0.03	Bailer	5 mL	5	930
				MW-16 Total Liters Removed:		0.930
<hr/>						

Former Angeles Chemical Co. Free Product Removal Data Summary

Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-18	1/29/2004	5.15	?	?	0	0
	2/8/2004	4.96	Bailer	4.5 gallons	17033	17033
	2/10/2004	3.76	Bailer	3 gallons	11355	28388
	2/11/2004	3.92	Pump	3.25 gallons	12301	40689
	2/13/2004	3.86	Pump	3.25 gallons	12301	52990
	2/14/2004	4.3	Pump	4.5 gallons	17033	70023
	2/16/2004	4	Pump	3.75 gallons	14194	84217
	2/17/2004	3.8	Pump	3.5 gallons	13248	97465
	2/18/2004	3.3	Pump	3 gallons	11355	108820
	3/4/2004	Not Measured	Pump	3 gallons	11355	120175
	3/5/2004	Not Measured	Pump	1.5 gallons	5678	125853
	3/9/2004	2.96	Pump	4 gallons	15140	140993
	3/10/2004	Not Measured	Pump	1 gallon	3785	144778
	3/19/2004	2.77	Bailer	3 gallons	11355	156133
	4/30/2004	3.5	Bailer	3.75 gallons	14194	170327
	5/27/2004	4.6	Bailer	2.5 gallons	9463	179790
	6/30/2004	2.99	Bailer	1.5 gallons	5678	185468
	7/9/2004	1.75	Bailer	1.0 gallon	3785	189253
	7/23/2004	2.04	Bailer	1.0 gallon	3785	193038
	8/13/2004	1.65	Bailer	0.75 gallons	2839	195877
	9/16/2004	0.23	Bailer	100 mL	100	195977
	9/28/2004	0.02	None	0	0	195977
	10/11/2004	0.02	None	0	0	195977
	10/22/2004	0.02	None	0	0	195977
	11/11/2004	0.22	Bailer	75 mL	75	196052
	11/24/2004	0.79	Bailer	500 mL	500	196552
	12/8/2004	0.96	Bailer	600 mL	600	197152
	12/21/2004	0.91	Bailer	600 mL	600	197752
	1/4/2005	1.22	Bailer	700 mL	700	198452
	1/20/2005	0.36	Bailer	200 mL	200	198652
	2/1/2005	0.66	Bailer	350 mL	350	199002
	2/16/2005	0.58	Bailer	300 mL	300	199302
	3/11/2005	0.13	Bailer	50 mL	50	199352
	4/2/2005	0.34	Bailer	200 mL	200	199552
	4/5/2005	0.04	Skimmer	380 mL	380	199932
	4/7/2005	0.04	Skimmer	380 mL	380	200312
	4/9/2005	0.04	Skimmer	380 mL	380	200692
	4/11/2005	0.04	Skimmer	380 mL	380	201072
	4/13/2005	0.04	Skimmer	380 mL	380	201452
	4/15/2005	0.04	Skimmer	380 mL	380	201832
	4/19/2005	0.04	Skimmer	380 mL	380	202212
	4/20/2005	0.04	Skimmer	380 mL	380	202592
	4/22/2005	0.04	Skimmer	380 mL	380	202972
	4/25/2005	0.04	Skimmer	380 mL	380	203352
	4/27/2005	0.04	Skimmer	380 mL	380	203732
	4/29/2005	0.04	Skimmer	380 mL	380	204112
	5/4/2005	0.04	Skimmer	380 mL	380	204492
	5/6/2005	0.04	Skimmer	380 mL	380	204872
	5/10/2005	0.03	Skimmer	300 mL	300	205172
	5/13/2005	0.03	Skimmer	300 mL	300	205472
	5/18/2005	0.03	Skimmer	300 mL	300	205772

5/21/2005	0.03	Skimmer	200 mL	200	205972
5/27/2005	0.04	Skimmer	200 mL	200	206172
6/3/2005	0.04	Skimmer	100 mL	100	206272
6/11/2005	0.03	Skimmer	100 mL	100	206372
6/18/2005	0.04	Skimmer	100 mL	100	206472
6/25/2005	0.04	Skimmer	100 mL	100	206572
7/2/2005	0.03	Skimmer	100 mL	100	206672
7/9/2005	0.03	Skimmer	100 mL	100	206772
7/16/2005	0.03	Skimmer	100 mL	100	206872
7/16/2005	0.03	Skimmer	100 mL	100	206972
7/23/2005	0.03	Skimmer	100 mL	100	207072
7/30/2005	0.03	Skimmer	100 mL	100	207172
8/6/2005	0.03	Skimmer	100 mL	100	207272
8/13/2005	0.03	Skimmer	100 mL	100	207372
8/20/2005	0.03	Skimmer	100 mL	100	207472
8/27/2005	0.02	Skimmer	100 mL	100	207572
9/3/2005	0.02	Skimmer	100 mL	100	207672
9/10/2005	0.02	Skimmer	50 mL	50	207722
9/19/2005	0.03	Skimmer	50 mL	50	207772
10/1/2005	0.03	Skimmer	50 mL	50	207822
10/8/2005	0.02	Skimmer	50 mL	50	207872
10/15/2005	0.02	Skimmer	50 mL	50	207922
10/24/2005	0.02	Skimmer	50 mL	50	207972
10/31/2005	0.02	Skimmer	50 mL	50	208022
11/12/2005	Sheen	Skimmer	0 mL	0	208022
MW-18 Total Liters Removed:					208.022

Former Angeles Chemical Co. Free Product Removal Data Summary

Well ID	Date	Product Thickness (feet)	Method of Removal	Volume Removed	Volume Removed (mL)	FP Removed to Date (mL)
MW-19	1/29/2004	1.75	?	?	0	0
	2/8/2004	0.43	Bailer	200 mL	200	200
	2/10/2004	0.7	Bailer	300 mL	300	500
	2/11/2004	0.27	Pump	100 mL	100	600
	2/13/2004	Not Measured	None	0	0	600
	2/14/2004	0.6	Pump	250 mL	250	850
	2/16/2004	0.3	Pump	100 mL	100	950
	2/17/2004	0.25	Pump	100 mL	100	1050
	2/18/2004	0.23	Pump	100 mL	100	1150
	3/19/2004	1.51	Bailer	0.75 gallons	2839	3989
	4/30/2004	2.05	Bailer	1.25 gallons	4731	8720
	5/27/2004	2.2	Bailer	1.25 gallons	4731	13451
	6/30/2004	2.04	Bailer	1 gallon	3785	17236
	7/9/2004	1.1	Bailer	0.5 gallons	1893	19129
	7/23/2004	0.77	Bailer	0.4 gallons	1514	20643
	8/13/2004	1.07	Bailer	0.5 gallons	1893	22535
	9/16/2004	1.38	Bailer	0.5 gallons	1893	24428
	9/28/2004	0.94	Bailer	400 mL	400	24828
	10/11/2004	0.75	Bailer	450 mL	450	25278
	10/22/2004	0.53	Bailer	250 mL	250	25528
	11/11/2004	0.66	Bailer	450 mL	450	25978
	11/24/2004	0.78	Bailer	500 mL	500	26478
	12/8/2004	0.88	Bailer	500 mL	500	26978
	12/21/2004	1	Bailer	600 mL	600	27578
	1/4/2005	1.05	Bailer	600 mL	600	28178
	1/20/2005	0.95	Bailer	500 mL	500	28678
	2/1/2005	0.65	Bailer	375 mL	375	29053
	2/16/2005	0.5	Bailer	300 mL	300	29353
	3/11/2005	0.35	Bailer	100 mL	100	29453
	4/2/2005	0.42	Bailer	250 mL	250	29703
	4/5/2005	0.04	Skimmer	380 mL	380	30083
	4/7/2005	0.04	Skimmer	380 mL	380	30463
	4/9/2005	0.04	Skimmer	380 mL	380	30843
	4/11/2005	0.04	Skimmer	380 mL	380	31223
	4/13/2005	0.04	Skimmer	380 mL	380	31603
	4/15/2005	0.04	Skimmer	380 mL	380	31983
	4/19/2005	0.04	Skimmer	380 mL	380	32363
	4/20/2005	0.04	Skimmer	380 mL	380	32743
	4/22/2005	0.04	Skimmer	380 mL	380	33123
	4/25/2005	0.04	Skimmer	380 mL	380	33503
	4/27/2005	0.04	Skimmer	380 mL	380	33883
	4/29/2005	0.04	Skimmer	380 mL	380	34263
	5/4/2005	0.04	Skimmer	380 mL	380	34643
	5/6/2005	0.04	Skimmer	380 mL	380	35023
	5/10/2005	0.03	Skimmer	300 mL	300	35323
	5/13/2005	0.03	Skimmer	300 mL	300	35623
	5/18/2005	0.03	Skimmer	300 mL	300	35923
	5/21/2005	0.03	Skimmer	200 mL	200	36123
	5/27/2005	0.05	Skimmer	200 mL	200	36323
	6/3/2005	0.04	Skimmer	300 mL	300	36623
	6/11/2005	0.04	Skimmer	200 mL	200	36823

	6/18/2005	0.04	Skimmer	200 mL	200	37023
	6/25/2005	0.04	Skimmer	200 mL	200	37223
	7/2/2005	0.03	Skimmer	200 mL	200	37423
	7/9/2005	0.03	Skimmer	200 mL	200	37623
	7/16/2005	0.03	Skimmer	200 mL	200	37823
	7/16/2005	0.03	Skimmer	200 mL	200	38023
	7/23/2005	0.03	Skimmer	200 mL	200	38223
	7/30/2005	0.03	Skimmer	200 mL	200	38423
	8/6/2005	0.03	Skimmer	200 mL	200	38623
	8/13/2005	0.03	Skimmer	200 mL	200	38823
	8/20/2005	0.03	Skimmer	200 mL	200	39023
	8/27/2005	0.02	Skimmer	150 mL	150	39173
	9/3/2005	0.02	Skimmer	150 mL	150	39323
	9/10/2005	0.02	Skimmer	150 mL	150	39473
	9/19/2005	0.03	Skimmer	150 mL	150	39623
	10/1/2005	0.03	Skimmer	150 mL	150	39773
	10/8/2005	0.02	Skimmer	100 mL	100	39873
	10/15/2005	0.02	Skimmer	100 mL	100	39973
	10/24/2005	0.02	Skimmer	100 mL	100	40073
	10/31/2005	0.02	Skimmer	100 mL	100	40173
	11/12/2005	0.02	Skimmer	250 mL	250	40423
	12/12/2005	0.02	Skimmer	200 mL	200	40623

0

MW-19 Total Liters Removed: 40.623

MW-21	12/8/2004	2.98	Bailer	1500 mL	1500	1500
	12/13/2004	0.22	Bailer	50 mL	50	1550
	12/21/2004	0.04	Bailer	5 mL	5	1555
	1/4/2005	0.04	None	0	0	1555
	2/1/2005	0.002	Bailer	3 mL	3	1558
	4/2/2005	0		0	0	

MW-21 Total Liters Removed: 1.558

MW-22	2/10/2004	0.04	None	0	0	0

MW-22 Total Liters Removed: 0.000

APPENDIX A

WELL GAUGING DATA

Project # 051216-341 Date 12/16/05 Client Clean Soils

Site 8915 Stamp Sonnen Ave., Santa Fe Springs

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #:	051216-SA1		Site:	Angeles Chemical Co.				
Sampler:	AB		Date:	12-16-05				
Well I.D.:	MW-4		Well Diameter:	2	3	(4)	6	8
Total Well Depth (TD):	40.69		Depth to Water (DTW):	33.24				
Depth to Free Product:			Thickness of Free Product (feet):					
Referenced to:	PVC	Grade	Flow Cell Type	STS				
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:						34.75		

Purge Method: Bailor
 Disposable Bailor
 Positive Air Displacement
 Electric Submersible
 Water
 2" Reciprocating Pump
 Extraction Pump
 Other _____

Sampling Method: Bailor
 Disposable Bailor
 Extraction Port
 Dedicated Tubing
 Other _____

Flow Rate: 1 GPM

4.8 (Gals.) X	3	= 14.4 Gals.
1 Case Volume	Specified Volumes	Calculated Volume

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or μS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1041	24.2	7.04	1966	8	0.57	-174.3	5	
			well dewatered	7	gallons			

Did well dewater? Yes No Gallons actually evacuated: 7

Sampling Date: 12-16-05 Sampling Time: 1415 Depth to Water: 33.45

Sample I.D.: MW-4 Laboratory: STS

Analyzed for: Other:

EB I.D. (if applicable): EB-1 @ $\frac{1}{10}$ Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ $\frac{1}{10}$ Analyzed for:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: 061216-SAM	Site: Angeles Chemical Co.
Sampler: TA	Date: 12/16/05
Well I.D.: MW-9	Well Diameter: 2 3 4 6 8
Total Well Depth (TD): 45.99	Depth to Water (DTW): 33.56
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	Flow Cell Type YSI 556 MPS
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 36.04	

Purge Method:	Bailer Disposable Bailer Positive Air Displacement Electric Submersible	Waterra 2" Endflo pump Extraction Pump	Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing
Flow Rate:	8.0 Gals./min		Other:
1 Case Volume	8.0 (Gals.) X 3	- 24.0 Gals.	Well Diameter Multiplier Well Diameter Multiplier
			1" 0.04 4" 0.65
			2" 0.16 6" 1.47
			3" 0.37 Other radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or μS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1331	Start Purge							
1335	22.82	6.70	2683	8	0.22	-127.7	8	
1339	22.86	6.71	2893	5	0.15	-133.1	16	
1343	22.79	6.76	2921	6	0.20	-130.2	24	

Did well dewater?	Yes	No	Gallons actually evacuated: 24	
Sampling Date: 12/16/05	Sampling Time: 1350	Depth to Water: 35.91		
Sample I.D.: MW-9	Laboratory: STS			
Analyzed for: See Scope	Other:			
EB I.D. (if applicable):	@	Time	Duplicate I.D. (if applicable):	
FB I.D. (if applicable):	@	Time	Analyzed for:	
D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: 051216-SA1	Site: Angeles Chemical Co.	
Sampler: AB	Date: 12-16-05	
Well I.D.: MW-10	Well Diameter: 2 3 (4) 6 8	
Total Well Depth (TD): 40.59	Depth to Water (DTW): 33.00	
Depth to Free Product:	Thickness of Free Product (feet):	
Referenced to: PVC	Grade	Flow Cell Type YST
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:		34.52

Purge Method: Bailer Water
 Disposable Bailer 2" RediFlo pump
 Positive Air Displacement Extraction Pump
 Electric Submersible Other _____

Sampling Method: Baile
Disposable Baile
Extraction Port
Dedicated Tubing

Flow Rate: 169 ml

Other.			
Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.63
2"	0.16	6"	1.47
3"	0.37	Other	$\text{radius}^2 \times 0.163$

Did well dewater? Yes No Gallons actually evacuated: 14

Sampling Date: 1-16-05 Sampling Time: 1405 Depth to Water: 33.16

Sample I.D.: MW-10 Laboratory: STS

Analyzed for: Other:

EB LD (if applicable): _____ @ _____ **Duplicate LD (if applicable):** _____

ED-1.D. (5-8-84) 111 @ Attached for

FB R.D. (if applicable): _____

D.O. (if req'd): Pre-purge: %_L Post-purge: %_L
 O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: 051216-SM	Site: Angeles Chemical Co.
Sampler: SF	Date: 12/16/05
Well I.D.: MW-11	Well Diameter: 2 3 4 6 8
Total Well Depth (TD): 39.81	Depth to Water (DTW): 32.71
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC Grade	Flow Cell Type VS1556 m/s
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 34.15	

Purge Method:	Bailer Disposable Bailer Positive Air Displacement Electric Submersible	Water	Sampling Method:	Bailer Disposable Bailer Extraction Port Dedicated Tubing		
		2" Radial pump Extraction Pump Other _____		Other: _____		
Flow Rate:	0.5 GPM					
1.1 (Gals.) X 3	- 3.3 Gals.		Well Diameter	Multiples	Well Diameter	Multiples
1 Case Volume	Specified Volume	Calculated Volume	1"	0.04	4"	0.65
			2"	0.16	6"	1.47
			3"	0.37	Other	$\text{radius}^2 * 0.163$

Time	Temp (°C)	pH	Cond. (mS or DS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1341	Start purge							
1344	23.75	6.60	1137	19	0.23	-152.7	1.5	
1346	24.01	6.63	1908	17	0.20	-161.7	2.5	
1348	24.08	6.65	1872	12	0.18	-163.4	3.5	

Did well dewater?	Yes	No	Gallons actually evacuated: 3.5	
Sampling Date:	12/16/05	Sampling Time:	1255	
Sampling Time:	1255	Depth to Water:	33.58	
Sample I.D.: MW-11	Laboratory: STS			
Analyzed for: See Scope	Other:			
EB I.D. (if applicable):	@ _{time}	Duplicate I.D. (if applicable):	MW-1	
FB I.D. (if applicable):	@ _{time}	Analyzed for:		
D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: 0512	Site: Angeles Chemical Co.
Sampler: SA	Date: 12/16/05
Well I.D.: MW-12	Well Diameter: 2 3 4 6 8
Total Well Depth (TD): 43.96	Depth to Water (DTW): 33.27
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: DYC Grade	Flow Cell Type 18 i 556 m/s
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 35.41	

Purge Method:	Bailer Disposable Baile Positive Air Displacement Electric Submersible	Water 2" Recirc Pump Extraction Pump Other _____	Sampling Method: Bailey Disposable Baile Extraction Port Dedicated Tubing Other: _____
Flow Rate= 0.5 GPM			
1.7 (Gals.) X 3 = 5.1 Gals.			
1 Case Volume Specified Volumes Calculated Volume			
Well Diameter	Multplier	Well Diameter	Multplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	$\text{radius}^2 * 0.163$

Time	Temp (°C)	pH	Cond. (mS or µS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1200	Start Purge						2	Odor off
1204	23.00	6.88	1149	33	0.16	-172.1	2	Oder
1208	23.45	6.86	1171	27	0.15	+98.2	4	
1212	23.49	6.85	1175	18	0.13	-213.6	6	

Did well dewater? Yes No Gallons actually evacuated: 6

Sampling Date: 12/16/05 Sampling Time: 11/5 Depth to Water: 33.47

Sample I.D.: MW-12 Laboratory: STS

Analyzed for: See Scope Other:

EB I.D. (if applicable): Duplicate I.D. (if applicable):

FB I.D. (if applicable): Analyzed for:

D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
------------------	------------	------	-------------	------

O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV
--------------------	------------	----	-------------	----

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7556

WELL MONITORING DATA SHEET

Project #: CS1216-SA1	Site: Angeles Chemical Co.
Sampler: SA	Date: 17/16/05
Well I.D.: MW-13	Well Diameter: 3 4 6 8
Total Well Depth (TD): 62.47	Depth to Water (DTW): 40.33
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC	Grade: Flow Cell Type YSI 556 MPS
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 44.75	

Purge Method:	Bailer Disposable Bailer Positive Air Displacement Electric Submersible	Water 2" Radiflo pump Extraction Pump Other _____	Sampling Method: Bailer Disposable Bailer Extraction Port Dedicated Tubing																
Flow Rate:	(10.7) Total 16 GPM		Other:																
	3.5 (Gals.) X 3	= 10.5 Gals. 1 Case Volume Specified Volumes Calculated Volume	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Well Diameter</th> <th>Multipier</th> <th>Well Diameter</th> <th>Multipier</th> </tr> </thead> <tbody> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.63</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>$\text{radius}^2 * 0.163$</td> </tr> </tbody> </table>	Well Diameter	Multipier	Well Diameter	Multipier	1"	0.04	4"	0.63	2"	0.16	6"	1.47	3"	0.37	Other	$\text{radius}^2 * 0.163$
Well Diameter	Multipier	Well Diameter	Multipier																
1"	0.04	4"	0.63																
2"	0.16	6"	1.47																
3"	0.37	Other	$\text{radius}^2 * 0.163$																

Time	Temp (°F)	pH	Cond. (mS or ppm)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1007	51°av+	Purge		0				
1010	22.63	6.92	1979	>1000	3.64	20.5	3.5	
1014	22.67	6.92	1982	885	3.80	7.1	7	
1017	22.70	6.92	1985	527	3.84	2.9	10.5	

Did well dewater? Yes No Gallons actually evacuated: 10.5

Sampling Date: 17/16/05 Sampling Time: 1025 Depth to Water: 40.48

Sample I.D.: MW-13 Laboratory: STS

Analyzed for: See Scope Other:

EB I.D. (if applicable): @ _{raw} Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ _{raw} Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #:	0512-16-S91	Site:	Angeles Chemical Co.
Sampler:	AB	Date:	12-16-05
Well I.D.:	MW-14	Well Diameter:	2 3 4 6 8
Total Well Depth (TD):	62.49	Depth to Water (DTW):	40.72
Depth to Free Product:		Thickness of Free Product (feet):	
Referenced to:	PVC	Grade:	Flow Cell Type ST
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 45.07			

Purge Method: Bailer
 Disposable Bailer
 Positive Air Displacement
 Electric Submersible Waterra
 2" Reciprocating Pump
 Extraction Pump
 Other _____

Sampling Method: Bailer
 Disposable Bailer
 Extraction Port
 Dedicated Tubing
 Other _____

Flow Rate: 16 PPM

3.5 (Gals.) X 3 = 10.5 Gals.
 1 Case Volume Specified Volumes Calculated Volume

Well Diameter	Multipier	Well Diameter	Multipier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1156	22.67	7.06	2230	55	4.26	-96.5	4	
1300	22.71	7.04	2224	38	4.24	-100.1	8	
1303	22.71	7.03	2223	29	4.28	-104.5	11	

Did well dewater? Yes No Gallons actually evacuated: 11

Sampling Date: 12-16-05 Sampling Time: 1310 Depth to Water: 40.79

Sample I.D.: MW-14 Laboratory: STS

Analyzed for: Other:

EB I.D. (if applicable): @ Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: OS12/6-3A1	Site: Angeles Chemical Co.
Sampler: SA	Date: 12/16/05
Well I.D.: MW-15	Well Diameter: 2 3 4 6 8
Total Well Depth (TD): 62.2	Depth to Water (DTW): 42.4
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: PVC	Flow Cell Type: VS1 SSN MPS
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 46.15	

Purge Method:	Bailer	Waterra	Sampling Method:	Bailer
	Disposable Bailer	2" Reciprocating pump		Disposable Bailer
	Positive Air Displacement	Extraction Pump		Extraction Port
	Electric Submersible	Other _____		Dedicated Tubing
Flow Rate:	1 GPM	Other:		
3.2 (Gals.) X 3 = 9.6 Gals.	1 Case Volume	Specified Volumes	Calculated Volume	Well Diameter Multiplier Well Diameter Multiplier 1" 0.04 4" 0.65 2" 0.16 6" 1.47 3" 0.37 Other $\pi r^2 = 0.163$

Time	Temp (°F)	pH	Cond. (mS or µS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1602	Start Purge							
1605	22.68	6.84	2186	41	0.18	-180.5	3.5	
1608	22.70	6.82	2178	30	0.16	-173.4	7	
1612	22.74	6.81	2168	29	0.13	-169.2	10	

Did well dewater? Yes No Gallons actually evacuated: 10

Sampling Date: 12/16/05 Sampling Time: 1620 Depth to Water: 42.19

Sample I.D.: MW-15 Laboratory: STS

Analyzed for: See Scope Other:

EB I.D. (if applicable): @ Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #:	DFU-16-541		Site:	Angeles Chemical Co.	
Sampler:	AB		Date:	12-16-05	
Well I.D.:	MW-16		Well Diameter:	2	3 4 6 8
Total Well Depth (TD):	45.22		Depth to Water (DTW):	32.23	
Depth to Free Product:			Thickness of Free Product (feet):		
Referenced to:	PVC	Grade	Flow Cell Type	y5T	
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 34.53					

Purge Method:	Bailer	Waterra	Sampling Method:	Bailer
	Disposable Bailer	2" Radiflo pump		Disposable Bailer
	Positive Air Displacement	Extraction Pump		Extraction Port
	Electric Submersible	Other _____		Dedicated Tubing
Flow Rate:	16 fm		Other:	
2.1 (Gals.) X 3	= 6.3 Gals.		Well Diameter	Multiplier
1 Case Volume	Specified Volumes	Calculated Volume	4"	0.63
			5"	1.47
			6"	radius ² * 0.163
			Other	

Time	Temp (°F)	pH	Cond. (mS or μ S)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1449	22.72	6.76	2188	836	0.27	-148.5	3	
1452	23.38	6.77	2290	>1000	0.81	-158.5	6	
1453	23.52	6.76	2336	>1000	0.69	-160.0	7	
1455	23.58	6.75	2362	>1000	0.62	-161.9	9	

Did well dewater?	Yes	No	Gallons actually evacuated:	9
Sampling Date:	12-16-05	Sampling Time:	1510	Depth to Water: 34.72
Sample I.D.:	MW-16		Laboratory:	ST5
Analyzed for:	Other:			
EB I.D. (if applicable):	@ <input checked="" type="checkbox"/>	Duplicate I.D. (if applicable):		
FB I.D. (if applicable):	@ <input checked="" type="checkbox"/>	Analyzed for:		
D.O. (if req'd):	Pre-purge:	mg/L	Post-purge:	mg/L
O.R.P. (if req'd):	Pre-purge:	mV	Post-purge:	mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #:	05/216-S41		Site:	Angeles Chemical Co.	
Sampler:	AB		Date:	12-16-05	
Well I.D.:	MW-17		Well Diameter:	2	3 4 6 8
Total Well Depth (TD):	66.26		Depth to Water (DTW):	38.87	
Depth to Free Product:			Thickness of Free Product (feet):		
Referenced to:	PVC	Grade	Flow Cell Type	YST	
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 44.31					

Purge Method:	Bailer	Waterra	Sampling Method:	Bailer		
	Disposable Bailer	2" Radflo pump		Disposable Bailer		
	Positive Air Displacement	Extraction Pump		Extraction Port		
	Electric Submersible	Other _____		Dedicated Tubing		
Flow Rate:	1 LPM		Other:			
44 (Gals.) X 3 = 132 Gals.			Well Diameter	Multiplier	Well Diameter	Multiplier
1 Case Volume	Specified Volumes	Calculated Volume	1"	0.04	4"	0.65
			2"	0.16	6"	1.47
			3"	0.37	Other	$\text{radius}^2 * 0.163$

Time	Temp (°F)	pH	Cond. (mS or μS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1338	22.70	6.97	2546	41	3.50	-105.6	5	
1343	22.81	6.97	2506	7	3.89	-108.6	10	
1346	22.83	6.97	2494	4	3.88	-110.0	14	

Did well dewater? Yes No Gallons actually evacuated: 14

Sampling Date: 12-16-05 Sampling Time: 1355 Depth to Water: 39.94

Sample I.D.: MW-17 Laboratory: STS

Analyzed for: Other:

EB I.D. (if applicable): @ Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #:	0512-16-SA/		Site:	Angeles Chemical Co.				
Sampler:	AB		Date:	12-16-05				
Well I.D.:	MW-20		Well Diameter:	2	3	4	6	8
Total Well Depth (TD):	67.33		Depth to Water (DTW):	39.68				
Depth to Free Product:			Thickness of Free Product (feet):					
Referenced to:	PVC	Grade	Flow Cell Type	ST				
DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]: 45.21								

Purge Method: Bailer Waterra
 Disposable Bailer 2" Redi-to-pump
 Positive Air Displacement Extraction Pump
 Electric Submersible Other _____

Sampling Method: Bailer Disposable Bailer
 Extraction Port Dedicated Tubing to Pump

Other: _____

Flow Rate: 16PM

$\frac{4.4 \text{ (Gals.)} \times 3}{1 \text{ Case Volume}} = 13.2 \text{ Gals.}$

Well Diameter	Multiplier	Well Diameter	Multiplier
1"	0.04	4"	0.65
2"	0.16	6"	1.47
3"	0.37	Other	radius ² * 0.163

Time	Temp (°F)	pH	Cond. (mS or μS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1038	22.91	7.05	2300	70	2.83	-91.5	5	
1043	22.99	7.04	2301	36	3.37	-97.0	10	
1047	22.96	7.03	2293	15	3.58	-102.4	14	

Did well dewater? Yes No Gallons actually evacuated: 14

Sampling Date: 12-16-05 Sampling Time: 1155 Depth to Water: 40 °C

Sample I.D.: MW-20 Laboratory: STS

Analyzed for: Other: _____

EB I.D. (if applicable): @ mg/L Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ mg/L Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558

WELL MONITORING DATA SHEET

Project #: 051216-SM	Site: Angeles Chemical Co.
Sampler: SA	Date: 12/16/05
Well I.D.: MW-26	Well Diameter <u>2</u> 3 4 6 8
Total Well Depth (TD): 39.65	Depth to Water (DTW): 38.98
Depth to Free Product:	Thickness of Free Product (feet):
Referenced to: <u>Pyd</u> Grade	Flow Cell Type VSI SS4 MAS

DTW with 80% Recharge [(Height of Water Column x 0.20) + DTW]:

Purge Method: <input checked="" type="checkbox"/> Bailer <input type="checkbox"/> Disposable Bailer <input type="checkbox"/> Positive Air Displacement <input type="checkbox"/> Electric Submersible	<input type="checkbox"/> Water <input type="checkbox"/> 2" RediPump <input type="checkbox"/> Extraction Pump <input type="checkbox"/> Other	Sampling Method: <input type="checkbox"/> Bailer <input checked="" type="checkbox"/> Disposable Bailer <input type="checkbox"/> Extraction Port <input type="checkbox"/> Dedicated Tubing																
Flow Rate: <u>No flow</u>		Other:																
(Gals.) X <u>1 Case Volume</u> = <u>Calculated Volume</u>		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="width: 25%;">Well Diameter</th> <th style="width: 25%;">Multiplier</th> <th style="width: 25%;">Well Diameter</th> <th style="width: 25%;">Multiplier</th> </tr> <tr> <td>1"</td> <td>0.04</td> <td>4"</td> <td>0.63</td> </tr> <tr> <td>2"</td> <td>0.16</td> <td>6"</td> <td>1.47</td> </tr> <tr> <td>3"</td> <td>0.37</td> <td>Other</td> <td>radius² * 0.163</td> </tr> </table>	Well Diameter	Multiplier	Well Diameter	Multiplier	1"	0.04	4"	0.63	2"	0.16	6"	1.47	3"	0.37	Other	radius ² * 0.163
Well Diameter	Multiplier	Well Diameter	Multiplier															
1"	0.04	4"	0.63															
2"	0.16	6"	1.47															
3"	0.37	Other	radius ² * 0.163															

Time	Temp (°C)	pH	Cond. (mS or µS)	Turbidity (NTUs)	D.O. (mg/L)	ORP (mV)	Gals. Removed	Observations
1205	20.01	6.52	1996	71000	6.10	-92.3	—	

Did well dewater? Yes No Gallons actually evacuated:

Sampling Date: 12/16/05 Sampling Time: 1205 Depth to Water: 38.98

Sample I.D.: MW-26 Laboratory: STS

Analyzed for: See Script Other:

EB I.D. (if applicable): @ Duplicate I.D. (if applicable):

FB I.D. (if applicable): @ Analyzed for:

D.O. (if req'd): Pre-purge: mg/L Post-purge: mg/L

O.R.P. (if req'd): Pre-purge: mV Post-purge: mV

Blaine Tech Services, Inc. 1680 Rogers Ave., San Jose, CA 95112 (800) 545-7558


TEST EQUIPMENT CALIBRATION LOG

TEST EQUIPMENT CALIBRATION LOG


PROJECT NAME			PROJECT NUMBER				
EQUIPMENT NAME	EQUIPMENT NUMBER	DATE/TIME OF TEST	STANDARDS USED	EQUIPMENT READING	CALIBRATED TO: OR WITHIN 10%	TEMP(°C)	INITIALS
YSI-556 Flow Cell	6	12/16/05 0915	pH 4 7 10	3.63 6.80 10.12	✓ ✓	14.3	88
		0918	Con. 3900 μS	9671 μS	✓	15.0	88
		0920	ORP 244mv	244.1	✓	15.0	88
↓	↓	0922	D.O.	97.1%	✓	15.1	88

APPENDIX B


Dissolved TPH-gas in 1st Water Wells




Dissolved TPH-gas in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved TPH-gas in A1 Wells




Dissolved TPH-gas in A1 Wells
(excluding MW-14, MW-15, MW-20 and MW-21 for smaller scale)




Total Dissolved VOCs in 1st Water Wells




**Total Dissolved VOCs in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19 and MW-26)**




Total Dissolved VOCs in A1 Wells




Total Dissolved VOCs in A1 Wells
(excluding MW-14, MW-15 and MW-21 for smaller scale)




Dissolved Benzene in 1st Water Wells




Dissolved Benzene in 1st Water Wells
(excluding MW-9, MW-10, MW-11, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved Benzene in A1 Wells




Dissolved Benzene in A1 Wells
(excluding MW-15 and MW-21 for smaller scale)




Dissolved Toluene in 1st Water Wells




Dissolved Toluene in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved Toluene in A1 Wells




Dissolved Toluene in A1 Wells
(excluding MW-14 for smaller scale)




Dissolved Toluene in A1 Wells
(excluding MW-14, MW-15 and MW-21 for smaller scale)




Dissolved PCE in 1st Water Wells




Dissolved PCE in 1st Water Wells
(excluding MW-16, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved PCE in A1 Wells




Dissolved PCE in A1 Wells
(excluding MW-13, MW-15, MW-21 and MW-25 for smaller scale)




Dissolved TCE in 1st Water Wells




Dissolved TCE in 1st Water Wells
(excluding MW-16, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved TCE in A1 Wells




Dissolved TCE in A1 Wells
(excluding MW-13, MW-15, MW-21 and MW-25 for smaller scale)




Dissolved 1,1,1-TCA in 1st Water Wells




Dissolved 1,1,1-TCA in 1st Water Wells
(excluding MW-10, MW-19 and MW-26 for smaller scale)




Dissolved 1,1,1-TCA in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved 1,1,1-TCA in A1 Wells




Dissolved 1,1,1-TCA in A1 Wells
(excluding MW-14, MW-20 and MW-21 for smaller scale)




Dissolved 1,4-Dioxane in 1st Water Wells




**Dissolved 1,4-Dioxane in 1st Water Wells
(excluding MW-9 and MW-16 for smaller scale)**




Dissolved 1,4-Dioxane in A1 Wells




**Dissolved 1,4-Dioxane in 1st Water Wells
(excluding MW-9 and MW-16 for smaller scale)**




Dissolved 1,1-DCA in 1st Water Wells




Dissolved 1,1-DCA in 1st Water Wells
(excluding MW-10, MW-11, MW-18 and MW-19 for smaller scale)




Dissolved 1,1-DCA in A1 Wells




Dissolved 1,1-DCA in A1 Wells
(excluding MW-14, MW-15, MW-20 and MW-21 for smaller scale)




Dissolved 1,1-DCE in A1 Wells
(excluding MW-14, MW-15, MW-20 and MW-21 for smaller scale)




Dissolved 1,1-DCE in 1st Water Wells




Dissolved 1,1-DCE in 1st Water Wells
(excluding MW-18, MW-19 and MW-26 for smaller scale)




Dissolved 1,1-DCE in A1 Wells




Dissolved Cis-1,2-DCE in 1st Water Wells




Dissolved Cis-1,2-DCE in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19, MW-22 and MW-26 for smaller scale)




Dissolved Cis-1,2-DCE in A1 Wells




Dissolved Cis-1,2-DCE in A1 Wells
(excluding MW-14, MW-15 and MW-21 for smaller scale)




Dissolved Vinyl Chloride in 1st Water




Dissolved Vinyl Chloride in 1st Water
(excluding MW-10, MW-11, MW-12, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved Vinyl Chloride in A1 Wells




Dissolved Vinyl Chloride in A1 Wells
(excluding MW-15 and MW-21 for smaller scale)




Dissolved Acetone in 1st Water Wells




Dissolved Acetone in 1st Water Wells
(excluding MW-10, MW-11, MW-18, MW-19 and MW-26 for smaller scale)




Dissolved Acetone in A1 Wells




Dissolved MEK in 1st Water Wells



Dissolved MEK in 1st Water Wells
(excluding MW-10, MW-18 and MW-19 for smaller scale)



Dissolved MEK in A1 Wells



APPENDIX C

ANCHEM 1302

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 1 of 2)
Reporting Unit: ppb

DATE ANALYZED		12-22	12-22-05	12-22-05		12-22-05	12-22-05
DILUTION FACTOR			10	10	250	100	1
LAB SAMPLE I.D.			BL512108-1	BL512108-2	BL512108-3	BL512108-4	BL512108-5
CLIENT SAMPLE I.D.			MW-8	MW-9	MW-10	MW-11	MW-12
COMPOUND	MDL	PQL	MB				
Dichlorodifluoromethane	2	5	ND	ND	ND	ND	ND
Chloromethane	2	5	ND	ND	ND	ND	ND
Vinyl Chloride	1	2	ND	4,050*	340	608	2,160*
Bromomethane	2	5	ND	ND	ND	ND	ND
Chloroethane	2	5	ND	111	ND	668	2,810
Trichlorofluoromethane	2	5	ND	ND	ND	ND	ND
1,1-Dichloroethene	2	5	ND	1,100	2,000	1,170	800
Iodomethane	2	5	ND	ND	ND	ND	ND
Methylene Chloride	2	5	ND	ND	ND	ND	ND
trans-1,2-Dichloroethene	2	5	ND	ND	ND	ND	ND
1,1-Dichloroethane	1	2	ND	33,000*	2,430	33,100	34,100*
2,2-Dichloropropane	2	5	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	2	5	ND	5,890*	594	4,380	5,350
Bromochloromethane	2	5	ND	ND	ND	ND	ND
Chloroform	2	5	ND	ND	ND	ND	ND
1,2-Dichloroethane	2	5	ND	ND	ND	ND	ND
1,1,1-Trichloroethane	2	5	ND	71.1	ND	2,570	ND
Carbon tetrachloride	2	5	ND	ND	ND	ND	ND
1,1-Dichloropropene	2	5	ND	ND	ND	ND	ND
Benzene	1	1	ND	286	36.4	ND	524
Trichloroethene	2	2	ND	ND	88.1	ND	ND
1,2-Dichloropropane	2	5	ND	ND	ND	ND	ND
Bromodichloromethane	2	5	ND	ND	ND	ND	ND
Dibromomethane	2	5	ND	ND	ND	ND	ND
trans-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND
cis-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND
1,1,2-Trichloroethane	2	5	ND	ND	ND	ND	ND
1,3-Dichloropropane	2	5	ND	ND	ND	ND	ND
Dibromochloromethane	2	5	ND	ND	ND	ND	ND
2-Chloroethylvinyl ether	2	5	ND	ND	ND	ND	ND
Bromoform	2	5	ND	ND	ND	ND	ND
Isopropylbenzene	2	5	ND	145	14.7J	ND	46.1
Bromobenzene	2	5	ND	ND	ND	ND	ND

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 2 of 2)

Reporting Unit: (ppb)

COMPOUND	MDL	PQL	MB	MW-8	MW-9	MW-10	MW-11	MW-12	MW-13
Toluene	1	1	ND	4,080*	ND	15,000	7,400	ND	ND
Tetrachloroethene	2	2	ND	ND	152	ND	ND	4.2	28.4
1,2-Dibromoethane(EDB)	2	5	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
1,1,1,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	ND	ND
Ethylbenzene	1	1	ND	1,780	ND	1,820	1,650	10.3	ND
Total Xylenes	2	2	ND	5,690*	ND	6,490	4,470	8.4	ND
Styrene	2	5	ND	ND	ND	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	ND	ND
1,2,3-Trichloropropane	2	5	ND	ND	ND	ND	ND	ND	ND
n-Propylbenzene	2	5	ND	232	ND	1,690	248	105	ND
2-Chlorotoluene	2	5	ND	ND	ND	ND	ND	ND	ND
4-Chlorotoluene	2	5	ND	ND	ND	ND	ND	ND	ND
1,3,5-Trimethylbenzene	2	5	ND	859	ND	680J	764	30.6	ND
tert-Butylbenzene	2	5	ND	ND	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	2	5	ND	4,200*	ND	2,680	2,240	49.6	ND
Sec-Butylbenzene	2	5	ND	ND	ND	ND	ND	4.4J	ND
1,3-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
p-Isopropyltoluene	2	5	ND	ND	ND	ND	ND	2.2J	ND
1,4-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
1,2-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
n-Butylbenzene	2	5	ND	41.1J	ND	ND	ND	5.9	ND
1,2,4-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
1,2-Dibromo-3-Chloropropane	2	5	ND	ND	ND	ND	ND	ND	ND
Hexachlorobutadiene	2	5	ND	ND	ND	ND	ND	ND	ND
Naphthalene	2	5	ND	282	ND	395J	172J	15.1	ND
1,2,3-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	ND
Acetone	5	25	ND	ND	ND	ND	ND	ND	ND
2-Butanone (MEK)	5	25	ND	ND	ND	ND	ND	ND	ND
Carbon disulfide	5	25	ND	ND	ND	ND	ND	ND	ND
4-Methyl-2-pentanone	5	25	ND	ND	ND	ND	ND	ND	ND
2-Hexanone	5	25	ND	ND	ND	ND	ND	ND	ND
Vinyl Acetate	5	25	ND	ND	ND	ND	ND	ND	ND
1,4-Dioxane	50	100	ND	ND	24,100	ND	ND	ND	ND
MTBE	2	2	ND	ND	ND	ND	ND	ND	ND
ETBE	2	2	ND	ND	ND	ND	ND	ND	ND
DIPE	2	2	ND	ND	ND	ND	ND	ND	ND
TAME	2	2	ND	ND	ND	ND	ND	ND	ND
T-Butyl Alcohol	10	10	ND	ND	ND	ND	ND	ND	ND

* Obtained from a higher dilution analysis.

MDL=Method Detection Limit; PQL=Practical Quantitation Limit; MB=Method Blank; ND=Not Detected (below DF × MDL), j=trace concentration.

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 1 of 2)
Reporting Unit: ppb

DATE ANALYZED			12-22	12-22-05	12-22-05	12-22-05	12-22-05
DILUTION FACTOR			2	1	20	1	1
LAB SAMPLE I.D.			BL512108-7	BL512108-8	BL512108-9	BL512108-10	BL512108-11
CLIENT SAMPLE I.D.			MW-14	MW-15	MW-16	MW-17	MW-20
COMPOUND	MDL	PQL					
Dichlorodifluoromethane	2	5	ND	ND	ND	ND	ND
Chloromethane	2	5	ND	ND	ND	ND	ND
Vinyl Chloride	1	2	22	418	721	ND	ND
Bromomethane	2	5	ND	ND	ND	ND	ND
Chloroethane	2	5	ND	30.4	ND	ND	ND
Trichlorofluoromethane	2	5	ND	ND	ND	ND	ND
1,1-Dichloroethene	2	5	262	89.1	3,480	11.3	57.4
Iodomethane	2	5	ND	ND	ND	ND	ND
Methylene Chloride	2	5	ND	ND	ND	ND	ND
trans-1,2-Dichloroethene	2	5	ND	ND	ND	ND	ND
1,1-Dichloroethane	1	2	77.2	262	3,990	ND	27.1
2,2-Dichloropropane	2	5	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	2	5	56.9	265	4,110	3.0J	7.3
Bromochloromethane	2	5	ND	ND	ND	ND	ND
Chloroform	2	5	ND	ND	ND	ND	ND
1,2-Dichloroethane	2	5	ND	ND	42.6J	ND	ND
1,1,1-Trichloroethane	2	5	ND	ND	83.2	ND	2.2J
Carbon tetrachloride	2	5	ND	ND	ND	ND	ND
1,1-Dichloropropene	2	5	ND	ND	ND	ND	ND
Benzene	1	1	ND	27.5	87.2	ND	ND
Trichloroethene	2	2	15.3	5.5	180	18.9	12.9
1,2-Dichloropropane	2	5	ND	ND	ND	ND	ND
Bromodichloromethane	2	5	ND	ND	ND	ND	ND
Dibromomethane	2	5	ND	ND	ND	ND	ND
trans-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND
cis-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND
1,1,2-Trichloroethane	2	5	ND	ND	ND	ND	ND
1,3-Dichloropropane	2	5	ND	ND	ND	ND	ND
Dibromochloromethane	2	5	ND	ND	ND	ND	ND
2-Chloroethylvinyl ether	2	5	ND	ND	ND	ND	ND
Bromoform	2	5	ND	ND	ND	ND	ND
Isopropylbenzene	2	5	ND	ND	ND	ND	ND
Bromobenzene	2	5	ND	ND	ND	ND	ND

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 2 of 2)
Reporting Unit: (ppb)

COMPOUND	MDL	PQL	MW-14	MW-15	MW-16	MW-17	MW-20	
Toluene	1	1	ND	54.5	ND	ND	1.7	
Tetrachloroethene	2	2	25.7	26.6	209	36.3	21.3	
1,2-Dibromoethane(EDB)	2	5	ND	ND	ND	ND	ND	
Chlorobenzene	2	5	ND	9.4	ND	ND	ND	
1,1,1,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	
Ethylbenzene	1	1	ND	7.2	242	ND	ND	
Total Xylenes	2	2	ND	30.8	90.2	ND	ND	
Styrene	2	5	ND	ND	ND	ND	ND	
1,1,2,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	
1,2,3-Trichloropropane	2	5	ND	ND	ND	ND	ND	
n-Propylbenzene	2	5	ND	ND	30.6J	ND	ND	
2-Chlorotoluene	2	5	ND	ND	ND	ND	ND	
4-Chlorotoluene	2	5	ND	ND	ND	ND	ND	
1,3,5-Trimethylbenzene	2	5	ND	ND	92.0J	ND	ND	
tert-Butylbenzene	2	5	ND	ND	217	ND	ND	
1,2,4-Trimethylbenzene	2	5	ND	5.7	1,450	ND	ND	
Sec-Butylbenzene	2	5	ND	ND	ND	ND	ND	
1,3-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	
p-Isopropyltoluene	2	5	ND	ND	ND	ND	ND	
1,4-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	
1,2-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	
n-Butylbenzene	2	5	ND	ND	77.6J	ND	ND	
1,2,4-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	
1,2-Dibromo-3-Chloropropane	2	5	ND	ND	ND	ND	ND	
Hexachlorobutadiene	2	5	ND	ND	ND	ND	ND	
Naphthalene	2	5	ND	ND	349	ND	ND	
1,2,3-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	
Acetone	5	25	42.0 J	ND	ND	ND	ND	
2-Butanone (MEK)	5	25	ND	ND	ND	ND	ND	
Carbon disulfide	5	25	ND	ND	ND	ND	ND	
4-Methyl-2-pentanone	5	25	ND	ND	ND	ND	ND	
2-Hexanone	5	25	ND	ND	ND	ND	ND	
Vinyl Acetate	5	25	ND	ND	ND	ND	ND	
1,4-Dioxane	50	100	ND	51.1	10,300	ND	ND	
MTBE	2	2	ND	ND	ND	ND	ND	
ETBE	2	2	ND	ND	ND	ND	ND	
DIPE	2	2	ND	ND	ND	ND	ND	
TAME	2	2	ND	ND	ND	ND	ND	
T-Butyl Alcohol	10	10	ND	ND	ND	ND	ND	

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 1 of 2)

Reporting Unit: ppb

DATE ANALYZED		12-22	12-22-05	12-22-05	12-22-05	12-22-05	12-22-05	
DILUTION FACTOR		1	1	1	50	50	1	
LAB SAMPLE I.D.		BL512108-13	BL512108-14	BL512108-15	BL512108-16	BL512108-17	BL512108-18	
CLIENT SAMPLE I.D.		MW-23@73.5	MW-24@69.5	MW-25@73.5	MW-26	DB-1	EB-1	
COMPOUND	MDL	PQL						
Dichlorodifluoromethane	2	5	ND	ND	ND	ND	ND	
Chloromethane	2	5	ND	ND	ND	ND	ND	
Vinyl Chloride	1	2	ND	ND	ND	ND	2,110	ND
Bromomethane	2	5	ND	ND	ND	ND	ND	
Chloroethane	2	5	ND	ND	ND	ND	2,870	ND
Trichlorofluoromethane	2	5	2.2J	23.9	11.0	313J	ND	ND
1,1-Dichloroethene	2	5	636*	50.6	8.2	9,210*	1,050	ND
Iodomethane	2	5	ND	ND	ND	ND	ND	
Methylene Chloride	2	5	ND	ND	ND	10,000	ND	ND
trans-1,2-Dichloroethene	2	5	ND	ND	ND	ND	ND	
1,1-Dichloroethane	1	2	51.5	5.9	ND	2,300	36,100*	ND
2,2-Dichloropropane	2	5	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	2	5	24.9	14.5	2.7	10,600*	5,770	ND
Bromochloromethane	2	5	ND	ND	ND	ND	ND	
Chloroform	2	5	ND	5.5	ND	ND	ND	ND
1,2-Dichloroethane	2	5	ND	ND	ND	ND	ND	
1,1,1-Trichloroethane	2	5	16.2	5.2	ND	4,710	ND	ND
Carbon tetrachloride	2	5	ND	ND	ND	ND	ND	
1,1-Dichloropropene	2	5	ND	ND	ND	ND	ND	
Benzene	1	1	ND	ND	ND	257	400	ND
Trichloroethene	2	2	19.3	86.0	41.0	2,160	ND	ND
1,2-Dichloropropane	2	5	ND	ND	ND	ND	ND	
Bromodichloromethane	2	5	ND	ND	ND	ND	ND	
Dibromomethane	2	5	ND	ND	ND	ND	ND	
trans-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND	
cis-1,3-Dichloropropene	2	5	ND	ND	ND	ND	ND	
1,1,2-Trichloroethane	2	5	ND	ND	ND	ND	ND	
1,3-Dichloropropane	2	5	ND	ND	ND	ND	ND	
Dibromochloromethane	2	5	ND	ND	ND	ND	ND	
2-Chloroethylvinyl ether	2	5	ND	ND	ND	ND	ND	
Bromoform	2	5	ND	ND	ND	ND	ND	
Isopropylbenzene	2	5	ND	ND	ND	ND	ND	
Bromobenzene	2	5	ND	ND	ND	ND	ND	

Client: Clean Soils Inc.
Project: Angeles Chemical Co.

Lab Job No.: BL512108 Date Reported: 01-03-2006
Matrix: Water Date Sampled: 12-16-2005

EPA 8260B (VOCs by GC/MS, Page 2 of 2)
Reporting Unit: (ppb)

COMPOUND	MDL	PQL	MW-23@73.5	MW-24@69.5	MW-25@73.5	MW-26	DB-1	EB-1	
Toluene	1	1	ND	ND	ND	16,400*	6,000	ND	
Tetrachloroethene	2	2	142	70.0	59.4	1,080	ND	ND	
1,2-Dibromoethane(EDB)	2	5	ND	ND	ND	ND	ND	ND	
Chlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
1,1,1,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	ND	
Ethylbenzene	1	1	ND	ND	ND	2,070	1,400	ND	
Total Xylenes	2	2	ND	ND	ND	6,070	3,830	ND	
Styrene	2	5	ND	ND	ND	ND	ND	ND	
1,1,2,2-Tetrachloroethane	2	5	ND	ND	ND	ND	ND	ND	
1,2,3-Trichloropropane	2	5	ND	ND	ND	ND	ND	ND	
n-Propylbenzene	2	5	ND	ND	ND	ND	170J	ND	
2-Chlorotoluene	2	5	ND	ND	ND	ND	ND	ND	
4-Chlorotoluene	2	5	ND	ND	ND	ND	ND	ND	
1,3,5-Trimethylbenzene	2	5	ND	ND	ND	ND	614	ND	
tert-Butylbenzene	2	5	ND	ND	ND	ND	ND	ND	
1,2,4-Trimethylbenzene	2	5	ND	ND	ND	594	1,920	ND	
Sec-Butylbenzene	2	5	ND	ND	ND	ND	ND	ND	
1,3-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
p-Isopropyltoluene	2	5	ND	ND	ND	ND	ND	ND	
1,4-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
1,2-Dichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
n-Butylbenzene	2	5	ND	ND	ND	ND	ND	ND	
1,2,4-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
1,2-Dibromo-3-Chloropropane	2	5	ND	ND	ND	ND	ND	ND	
Hexachlorobutadiene	2	5	ND	ND	ND	ND	ND	ND	
Naphthalene	2	5	ND	ND	ND	ND	140J	ND	
1,2,3-Trichlorobenzene	2	5	ND	ND	ND	ND	ND	ND	
Acetone	5	25	ND	ND	ND	9,440	ND	ND	
2-Butanone (MEK)	5	25	ND	ND	ND	4,120	ND	ND	
Carbon disulfide	5	25	ND	ND	ND	ND	ND	ND	
4-Methyl-2-pentanone	5	25	ND	ND	ND	7,120	ND	ND	
2-Hexanone	5	25	ND	ND	ND	ND	ND	ND	
Vinyl Acetate	5	25	ND	ND	ND	ND	ND	ND	
1,4-Dioxane	50	100	ND	ND	ND	ND	ND	ND	
MTBE	2	2	ND	ND	ND	ND	ND	ND	
ETBE	2	2	ND	ND	ND	ND	ND	ND	
DIPE	2	2	ND	ND	ND	ND	ND	ND	
TAME	2	2	ND	ND	ND	ND	ND	ND	
T-Butyl Alcohol	10	10	ND	ND	ND	ND	ND	ND	

01-03-2006

Client: Clean Soils Inc.

Lab Job No.:

BL512108

Project: Angeles Chemical Co.

Project Site: 8915 Sorensen Ave., Santa Fe Springs, CA

Date Sampled: 12-16-2005

Matrix: Water

Date Received: 12-16-2005

Batch No.: BML21-GW1

Date Analyzed: 12-21-2005

EPA 8015M (Gasoline)
Reporting Units: µg/L (ppb)

Sample ID	Lab ID	C4-C12 (Gasoline Range)	Method Detection Limit	PQL
Method Blank		ND	50	50
MW-8	BL512108-1	64,600	50	50
MW-9	BL512108-2	3,600	50	50
MW-10	BL512108-3	87,100	50	50
MW-11	BL512108-4	238,000	50	50
MW-12	BL512108-5	1,470	50	50
MW-13	BL512108-6	92.1	50	50
MW-14	BL512108-7	180	50	50
MW-15	BL512108-8	885	50	50
MW-16	BL512108-9	21,800	50	50
MW-17	BL512108-10	104	50	50
MW-20	BL512108-11	81.5	50	50
MW-23@73.5	BL512108-13	288	50	50
MW-24@69.5	BL512108-14	341	50	50
MW-25@73.5	BL512108-15	165	50	50
MW-26	BL512108-16	158,000	50	50
DB-1	BL512108-17	241,000	50	50
EB-1	BL512108-18	ND	50	50

PQL: Practical Quantitation Limit.

01-03-2006

Client: Clean Soils Inc. Lab Job No.: BL512108

Project: Angeles Chemical Co.

Project Site: 8915 Sorensen Ave., Santa Fe Springs, CA

Date Sampled: 12-16-2005

Matrix: Water

Date Received: 12-16-2005

Analytical Test Results

Analyte	EPA Method	Date Analyzed	Unit	MW-8	MW-9	MW-10	MW-11	MW-12	Reporting Limit
				BL512108-1	BL512108-2	BL512108-3	BL512108-4	BL512108-5	
Ethylene	GC/FID	12-19-05	ug/L	804	46	193	1,803	ND	5
TDS	160.1	12-20-05	mg/L	136	1,550	509.4	630	374	2
Nitrate	352.1	12-16-05	mg/L	10.8	16.3	4.11	8.20	6.70	0.01
Sulfate	375.4	12-19-05	mg/L	4.82	224	11.4	ND	76.6	1.0
Total Iron	7380	12-19-05	mg/L	0.11	ND	0.59	0.61	ND	0.1
Manganese	7460	12-19-05	mg/L	2.07	0.23	2.49	6.05	2.62	0.05
Ferrous Iron	Colorimetry	12-16-05	mg/L	ND	ND	ND	0.10	ND	0.05

Analyte	EPA Method	Date Analyzed	Unit	MW-13	MW-15	MW-17	MW-20		Reporting Limit
				BL512108-6	BL512108-8	BL512108-10	BL512108-11		
Ethylene	GC/FID	12-19-05	ug/L	ND	121	ND	ND		5
TDS	160.1	12-20-05	mg/L	516	----	1,070	1,020		2
Nitrate	352.1	12-16-05	mg/L	12.2	6.86	13.9	17.6		0.01
Sulfate	375.4	12-19-05	mg/L	98.8	37.0	76.2	64.4		1.0
Total Iron	7380	12-19-05	mg/L	ND	ND	ND	ND		0.1
Manganese	7460	12-19-05	mg/L	0.25	0.20	ND	0.40		0.05
Ferrous Iron	Colorimetry	12-16-05	mg/L	ND	ND	ND	ND		0.05

ND: Not Detected (at the specified limit).

01-03-2006

Client: Clean Soils Inc. Lab Job No.: BL512108
Project: Angeles Chemical Co.
Project Site: 8915 Sorensen Ave., Santa Fe Springs, CA Date Sampled: 12-16-2005
Matrix: Water Date Received: 12-16-2005
Batch No.: 1222-BNA Date Analyzed: 12-22-2005

Modified EPA 8270C (1,4-Dioxane by GC/MS)
Reporting Units: µg/L (ppb)

Sample ID	Lab ID	1,4-Dioxane	Method Detection Limit	PQL
Method Blank		ND	2	3.0
MW-8	BL512108-1	167	2	3.0
MW-10	BL512108-3	124	2	3.0
MW-12	BL512108-5	ND	2	3.0
MW-13	BL512108-6	ND	2	3.0
MW-17	BL512108-10	ND	2	3.0
MW-20	BL512108-11	96.5	2	3.0

ND: Not Detected (at the specified limit)

01-03-2006

EPA 8015M

Batch QA/QC Report

Client: Clean Soils Inc.

Lab Job No.: BL512108

Project: Angeles Chemical Co.

Matrix: Water

Lab Sample ID: GP512115-1

Batch No.: BML22-GW1

Date Analyzed: 12-22-2005

I. MS/MSD Report

Unit: ppb

Analyte	Sample Conc.	Spike Conc.	MS	MSD	MS %Rec.	MSD %Rec.	% RPD	%RPD Accept. Limit	%Rec Accept. Limit
TPH-g	ND	1,000	988	1,010	98.8	101.0	2.2	30	70-130

II. LCS Result

Unit: ppb

Analyte	LCS Value	True Value	Rec.%	Accept. Limit
TPH-g	886	1,000	88.6	80-120

ND: Not Detected.

01-03-2006

Modified EPA 8270C (1,4-Dioxane by GC/MS)

Batch QA/QC Report

Client: Clean Soils Inc.
Project: Angeles Chemical Co.
Matrix: Water
Batch No.: 1222-BNA

Lab Job No.: BL512108
Lab Sample ID: ST1222-1
Date Analyzed: 12-22-2005

LCS/LCSD Result

Unit: ppb

Analyte	Sample Conc.	Spike Conc.	LCS	LCSD	LCS %Rec.	LCSD %Rec.	% RPD	%RPD Accept. Limit	%Rec Accept. Limit
1,4-Dioxane	ND	10.0	10.8	10.5	108.3	104.7	3.4	30	70-130

ND:Not Detected

01-03-2006

EPA 8260B

Batch QA/QC Report

Client: Clean Soils Inc.

Project: Angeles Chemical Co.

Matrix: Water

Batch No: 1222-VQBW1

Lab Job No.: BL512108

Lab Sample ID: GP512115-1

Date Analyzed: 12-22-2005

I. MS/MSD Report

Unit: ppbAnalyte	Sample Conc.	Spike Conc.	MS	MSD	MS %Rec.	MSD %Rec.	% RPD	%RPD Accept. Limit	%Rec Accept. Limit
1,1-Dichloroethene	ND	20	20.5	15.9	102.5	79.5	25.3	30	70-130
Benzene	ND	20	21.8	17.4	109.0	87.0	22.4	30	70-130
Trichloro-ethene	ND	20	18.6	15.6	93.0	78.0	17.5	30	70-130
Toluene	ND	20	23.0	17.0	115.0	85.0	30.0	30	70-130
Chlorobenzene	ND	20	22.1	17.5	110.5	87.5	23.2	30	70-130

II. LCS Result

Unit: ppb

Analyte	LCS Value	True Value	Rec.%	Accept. Limit
1,1-Dichloroethene	46.3	50	92.6	80-120
Benzene	49.4	50	98.8	80-120
Trichloro-ethene	43.7	50	87.4	80-120
Toluene	51.0	50	102.0	80-120
Chlorobenzene	49.1	50	98.2	80-120

ND: Not Detected.

01-03-2006

**Ethylene by GC/FID
Batch QA/QC Report**

Client: Clean Soils Inc.
Project: Angeles Chemical Co.
Matrix: Water
Batch No.: FL19A

Lab Job No.: BL512108
Lab Sample ID: BL512108-6
Date Analyzed: 12-19-2005

I. Sample/Sample Dup Report
Reporting Units: $\mu\text{g/L}$

Analyte	MB	Sample Conc.	Sample Duplicate	% RPD	%RPD Accept. Limit
Ethylene	ND	ND	ND	2.1	30

II. LCS Result

Reporting Units: $\mu\text{g/L}$

Analyte	LCS Report Value	True Value	Rec.%	Accept. Limi
Ethylene	4,249	4,170	101.9	80-120

ND: Not Detected.



AmeriChem
Testing
Laboratory

1761 N. Batavia St.
Orange, CA 92865

(714) 921-1550
FAX: (714) 921-4770

Analytical Report

REPORT NUMBER: AL-7443

CLIENT:

STS Environmental Lab.
7801 Telegraph Rd. suite J
Montebello, CA 90640

REPORT ON:

Water sample
BL-512108, 12/16/05

DATE RECEIVED: 12/19/05

DATE REPORTED: 12/21/05

ANALYSIS : Chloride, DET. LIMIT: 0.1mg/l, METHOD: EPA 325.3

ANALYSIS : Sulfide, DET. LIMIT: 0.05mg/l, METHOD: EPA 376.1

ANALYSIS : Caronate, DET. LIMIT: 2.0mg/l, METHOD: Standard Method 4500

ANALYSIS : Bicarbonate, DET. LIMIT: 2.0mg/l, METHOD: Standard Method 4500

ANALYSIS : Alkalinity, DET. LIMIT: 1.0mg/l, METHOD: EPA 310.1

ANALYSIS	TEST RESULT, mg/l									
	-1	-2	-3	-4	-5	-6	-8	-10	-11	
Chloride	125	294	65.3	98.0	45.6	65.3	144	125	114	
Sulfide	0.48	ND	ND	0.16	ND	ND	ND	ND	ND	
Carbonate	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Bicarbonate	355	363	332	351	194	229	320	256	271	
Total Alkalinity	583	595	545	573	318	375	525	420	445	

Peter T. Wu

Peter T. Wu
Lab Director

SOUTHLAND TECHNICAL SERVICES, INC.

CHAIN OF CUSTODY RECORD

Page 1 of 1Lab Job Number BLS12108

Client: <u>Southland Technical Services, Inc.</u> Address: <u>7801 Telegraph Rd #L Montebello, CA 90640</u> Report Attention: <u>Roger Wking</u> Phone: <u>323-888-0728</u> Fax: <u>323-888-1509</u> Sampled by: _____							Analyses Requested 602/8021 (BTEX/MTBE) 8015M (Gasoline) 8015M (Diesel) 8260B (VOCs) 8260B (Oxygenates, BTEX) 8260B (MTBE Confirm.) Chloride Sulfide Alkalinity Standard Methanol Carbonate & Bicarbonate							T.A.T. Requested <input type="checkbox"/> Rush 8-12-24 hours <input type="checkbox"/> 2-3 days <input type="checkbox"/> Normal		
Project Name/No. <u>BLS12108</u>	Project Site	Client Sample ID	Lab Sample ID	Sample Collect		Matrix Type	Sample Preserve	No.,type* & size of container	Remarks							
				Date	Time											
<u>BLS12108-1</u>		<u>7/16/03</u>		<u>H₂O</u>		<u>1P</u>			X	X	X	X				<u>MW-8</u>
-2		"	"	"	"	"			X	X	X	X				<u>MW-9</u>
-3		"	"	"	"	"			X	X	X	X				<u>MW-10</u>
-4		"	"	"	"	"			X	X	X	X				<u>MW-11</u>
-5		"	"	"	"	"			X	X	X	X				<u>MW-12</u>
-6		"	"	"	"	"			X	X	X	X				<u>MW-13</u>
-8		"	"	"	"	"			X	X	X	X				<u>MW-15</u>
-10		"	"	"	"	"			X	X	X	X				<u>MW-17</u>
-11		"	"	"	"	"			X	X	X	X				<u>MW-20</u>
Relinquished by <u>L. Wking</u> Company <u>SLS</u>		Date <u>7/14/03</u>	Time <u>PM</u>	Received by <u>J. L. Lunn</u>	Company <u>MTS</u>		Container types: M=Metal Tube A=Air Bag P=Plastic bottle G=Glass bottle V=VOA vial									
Relinquished by		Company	Date	Time	Received by	Company										

Note: Samples are discarded 30 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client's expense.
 Distribution: WHITE with report, PINK to courier.



ASSOCIATED LABORATORIES
806 North Batavia - Orange, California 92868 - 714/771-6900

FAX 714/538-1209

CLIENT Southland Technical Services (6304)

LAB REQUEST 161813

ATTN: Roger Wang
7801 Telegraph Rd.- Suite L
Montebello, CA 90640

REPORTED 12/31/2005
RECEIVED 12/19/2005

PROJECT BL512108

SUBMITTER Client

COMMENTS

This laboratory request covers the following listed samples which were analyzed for the parameters indicated on the attached Analytical Result Report. All analyses were conducted using the appropriate methods as indicated on the report. This cover letter is an integral part of the final report.

<u>Order No.</u>	<u>Client Sample Identification</u>
674927	BL512108-1
674928	BL512108-2
674929	BL512108-3
674930	BL512108-4
674931	BL512108-5
674932	BL512108-6
674933	BL512108-10
674934	BL512108-11
674935	Laboratory Method Blank

Thank you for the opportunity to be of service to your company. Please feel free to call if there are any questions regarding this report or if we can be of further service.

ASSOCIATED LABORATORIES by,

Edward S. Behare, Ph.D.
Vice President

NOTE: Unless notified in writing, all samples will be discarded by appropriate disposal protocol 30 days from date reported.

The reports of the Associated Laboratories are confidential property of our clients and may not be reproduced or used for publication in part or in full without our written permission. This is for the mutual protection of the public, our clients, and ourselves.

TESTING & CONSULTING
Chemical
Microbiological
Environmental

Order #: 674927

Client Sample ID: BL512108-1

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	23	1.0	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	24	1.0	mg/L	12/23/05 QP

Order #: 674928

Client Sample ID: BL512108-2

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	22	1.0	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	21	1.0	mg/L	12/23/05 QP

Order #: 674929

Client Sample ID: BL512108-3

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	17	1.0	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	14	1.0	mg/L	12/23/05 QP

DLR = Detection limit for reporting purposes, ND = Not Detected below indicated detection limit

ASSOCIATED LABORATORIES

Analytical Results Report

Lab Request 161813 results, page 1 of 3



ANCHEM 1319

Order #: 674930

Client Sample ID: BL512108-4

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
---------	--------	-----	-------	--------------

415.1 Total Organic Carbon (TOC)

Total Organic Carbon	30	1.0	mg/L	12/23/05	QP
----------------------	----	-----	------	----------	----

9060 Total Organic Carbon (TOC)

Dissolved Organic Carbon	29	1.0	mg/L	12/23/05	QP
--------------------------	----	-----	------	----------	----

Order #: 674931

Client Sample ID: BL512108-5

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
---------	--------	-----	-------	--------------

415.1 Total Organic Carbon (TOC)

Total Organic Carbon	4.1	1.0	mg/L	12/23/05	QP
----------------------	-----	-----	------	----------	----

9060 Total Organic Carbon (TOC)

Dissolved Organic Carbon	4.4	1.0	mg/L	12/23/05	QP
--------------------------	-----	-----	------	----------	----

Order #: 674932

Client Sample ID: BL512108-6

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
---------	--------	-----	-------	--------------

415.1 Total Organic Carbon (TOC)

Total Organic Carbon	3.7	1.0	mg/L	12/23/05	QP
----------------------	-----	-----	------	----------	----

9060 Total Organic Carbon (TOC)

Dissolved Organic Carbon	5.0	1.0	mg/L	12/23/05	QP
--------------------------	-----	-----	------	----------	----

DLR = Detection limit for reporting purposes, ND = Not Detected below indicated detection limit



Order #: 674933

Client Sample ID: BL512108-10

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	17	1.0	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	15	1.0	mg/L	12/23/05 QP

Order #: 674934

Client Sample ID: BL512108-11

Matrix: WATER

Date Sampled: 12/16/2005

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	9.8	1.0	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	8.7	1.0	mg/L	12/23/05 QP

Order #: 674935

Client Sample ID: Laboratory Method Blank

Matrix: WATER

Analyte	Result	DLR	Units	Date/Analyst
415.1 Total Organic Carbon (TOC)				
Total Organic Carbon	ND	0.5	mg/L	12/23/05 QP
9060 Total Organic Carbon (TOC)				
Dissolved Organic Carbon	ND	0.5	mg/L	12/23/05 QP

DLR = Detection limit for reporting purposes, ND = Not Detected below indicated detection limit

ASSOCIATED LABORATORIES

Analytical Results Report

Lab Request 161813 results, page 3 of 3



ANCHEM 1321

**ASSOCIATED LABORATORIES
QA REPORT FORM**

QC Sample: 161813-5

Matrix: WATER

Prep. Date: December 23, 2005

Analysis Date: December 23, 2005

ID#'s in Batch: LR 161813

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RESULT

Reporting Units = mg/L

Test	Method	Sample Result	Spike Added	Matrix Spike	Matrix Spike Dup	%Rec MS	%Rec MSD	RPD
TOC	415.1 / 9060	4	10	13.6	14.7	96	107	8

ND = "U" - Not Detected

RPD = Relative Percent Difference of Matrix Spike and Matrix Spike Duplicate

%REC-MS & MSD = Percent Recovery of Matrix Spike & Matrix Spike Duplicate

%REC LIMITS = 80 - 120

RPD LIMITS = 20

PREPARATION BLANK / LAB CONTROL SAMPLE RESULTS

PREP BLK	LCS				
	Value	Result	True	%Rec	L.Limit
ND	9.7	10	97	80%	120%

Value = Preparation Blank Value; ND = Not-Detected

LCS Result = Lab Control Sample Result

True = True Value of LCS

L.Limit / H.Limit = LCS Control Limits



ASSOCIATED LABORATORIES

806 N. Batavia • Orange, CA 92868
(714) 771-6900 • Fax: (714) 538-1209

CHAIN OF CUSTODY RECORD

Date 12/19/05 Page 1 of 1

Relinquished by: (Signature)

Received by: (Signature)

Date/Time

I hereby authorize the performance of the above indicated work.

RETIRED BY SIGNATURE

Received by Laboratory for analysis:
(Signature)

Date/Time: 10/25

Special Instructions:

DISTRIBUTION: White with report. Yellow to AL,
Pink to Courier